Contractors are responsible for checking all dimensions on site prior to work commencing.Due to areas of the structure being covered, unexposed or otherwise inaccessible the notes / specifications of existing materials are subject to confirmation of site when it is feasible to expose the relevant areas of construction. All material schedules are given in good faith and for pricing purposes only. It is the responsibility of the contractor to check their accuracy before ordering any materials. Remway Design accepts no responsibility for the accuracy of these material schedules.

a2

0m 4m 8m 12m 16m 20m

VISUAL SCALE 1:200 @ a2

F.F.L +3.75

F.F.L +4.00

F.F.L +5.00

+3.50

+5.70

Proposed Site Levels are to be re-graded from +5.70 at edge of footpath with a constant slope downwards into the site to a level of +3.50 at Anglian Water Sewer location

All stormwater to discharge to soakaways min.5m from any building

66 Barrier Bank | Cowbit

Site Levels

Drg No 3050 - RM - S05

remway Design Ltd