STONE GATE

NATIVE HEDGE for sheet 3
3 plants per metre (Double staggered row)

Species:	Size:	Height:	Plant %:	No's:
Crataegus monogyna	Transplant 3yrs	60-80cm	70	184
Cornus alba	2L	60-80cm	15	39
Corylus avellana	O.G	60-80cm	10	26
Viburnum opulus	O.G	60-80cm	5	14

Planting Schedule for Sheet 3

	Qty	Species	Size	Specification
		TREES		
Bp	2	Betula pendula	175-200	10L Container Grown
C	2	Crataegus laevigata 'Plena'	8-10	Standard
Pa	4	Prunus avium 'Plena'	8-10	Standard
M	3	Malus tschonskii	8-10	Standard
S	2	Sorbus aucuparia Asplenifolia	10-12	Selected Std
		SPECIMEN SHRUBS		
Am	5	Amelanchier canadensis	80-100cm	10L Container Grown
Cc	8	Cotinus coggygria	60-80cm	10L Container Grown
Cl	10	Cotoneaster lacteus	60-80cm	10L Container Grown
Ia	3	Ilex x altaclerensis Golden King	60-80cm	10L Container Grown
Po	2	Pyracantha 'Orange Glow'	80-100cm	10L Container Grown
		CLIMBERS		
	2	Parthenocissus quinquefolia	100-150cm	10L Container Grown

	Qty	Species	Size	Specification
		HEDGING PLANTS		
	108	Crataegus monogyna	60-80cm	3yr. Transplant
	23	Cornus alba	40-60cm	2L Container Grown
	15	Corylus avellana	60-80cm	O.G.
	8	Viburnum opulus	60-80cm	O.G.
		SHRUBS		
	18	Prunus laurocerasus 'Otto Luyken'	80-100cm	10L Container Grown
	583	Vinca minor alba	30-40cm	2L Container Grown
	150	Vinca autopurpurea	30-40cm	2L Container Grown

24no. Plants
Refer: Native Hedge Mix
(3 Plants per M.)

73no. Plants
Refer: Native Hedge Mix
(3 Plants per M.)

57no. Plants
Refer: Native Hedge Mix
(3 Plants per M.)

295 no. Vinca minor alba
@ 300 c s

1 no. Parthenocissus quinquefolia

288 no. Vinca minor alba
@ 300 c s

150 no. Vinca minor atropurpurea
@ 300 c s


18no. Prunus laurocerasus
'Otto Luyken'
@ 750mm c s

1 no. Parthenocissus quinquefolia

(Refer to other sheet for planting details)

Key:

- Existing Trees & Shrubs
- Proposed Specimen Trees & Shrubs
- Proposed Shrubs
- Proposed Hedge
- Proposed 1.8m c b Fence
- Grass
- Page Dividing Line



Allison Homes

Planting Layout **Plot 2 Cowbit**

Scale 1:200 December 1999

Dwg No.: 233/75/SHG6

Town & Country Planning
Ecology
Landscape Architecture

Robert Doughty Consultancy

32 High Street, Helpringham, Sleaford NG34 ORA Tel. (01529) 421646 Fax. (01529) 421355

Planting Schedule for Sheet 4

	Qty	Species	Size	Specification
		TREES		
Bp	6	Betula pendula	175-200cm	10l Container Grown
G	1	Crataegus laevigata 'Plena'	8-10	Standard
Pa	1	Prunus avium 'Plena'	8-10	Standard
M	1	Malus tschonoskii	8-10	Standard
S	4	Sorbus aucuparia 'Asplenifolia'	10-12	Selected Std
		SPECIMEN SHRUBS		
Am	4	Amelanchier canadensis	100-150cm	10l Container Grown
Cc	4	Colinus coggygria	60-80cm	10l Container Grown
Cl	70	Cotoneaster [illegible]lis	60-80cm	10l Container Grown
Ia	4	Ilex x altaclerensis 'Golden King'	80-100cm	10l Container Grown
Po	6	Pittosporum 'Orange Glow'	80-100cm	10l Container Grown


Key:

- Existing Trees & Shrubs
- Proposed Specimen Trees & Shrubs
- Proposed Shrubs
- Proposed Hedge
- Proposed 1.8m c.b. Fence
- Grass
- Page Dividing Line

(Refer to other sheet for planting details)

PLANTING NOTES

1. All trees are to be adequately staked and tied and half a bag of peat free tree planting compost incorporated into the backfill for each tree hole
2. A top dressing of 'Enmag' fertilizer shall be made to all shrub areas, hedges and trees following planting strictly in accordance with the manufacturer's instructions.



Allison Homes

Planting Layout **Plot 2 Cowbit**

Scale 1:200 December 1999

Dwg No.: 233/75/SHG7

Town & Country Planning
Ecology
Landscape Architecture
Robert Doughty Consultancy
32 High Street, Helpringham, Sleaford NG34 0RA Tel: (01529) 421646 Fax: (01529) 421358

PLANTING SCHEDULE for SHEET 2

	Qty.	Species	Size	Specification
		TREES		
Bp	2	Betula pendula	175-200cm (Height)	10L Container Grown
C	6	Crataegus laevigata Plena	10-12cm (Girth)	Standard
Pa	1	Prunus avium Plena	10-12cm (Girth)	Standard
M	3	Malus sylvestris	10-12cm (Girth)	Selected Std.
S		Sorbus Asplenifolia	10-12cm (Girth)	Selected Std.
		SPECIMEN SHRUBS		
Ac	11	Amelanchier canadensis	00-150cm (Height)	10L Container Grown
Cc	9	Cotinus coggygria	60-80cm (Height)	10L Container Grown
Cm	15	Cotoneaster microphyllus	40-60cm (Height)	10L Container Grown
Ia	14	Ilex x altaclerensis Golden King	60-80cm (Height)	10L Container Grown
Po		Pyracantha Orange Glow	80-100cm (Height)	
		CLIMBERS		
	6	Parthenocissus quinquefolia	100-150cm (Height)	10L Container Grown

	Qty.	Species	Size	Specification
		HEDGING PLANTS		
	52	Viburnum opulus	60-80cm	10L Container Grown
		SHRUBS		
	84	Vinca minor alba	30-40cm(Height)	2L Container Grown
	31	Vinca minor autopurpurea	30-40cm(Height)	1L Container Grown
		SHRUB BOUNDARY		
Ca	6	Corylus avellana	80-100cm (Height)	Root balled
Csp	3	Cornus sanguinea	60-80cm (Height)	Root balled
Cs	4	Cotoneaster simonsii	40-60cm (Height)	Root balled

Key:

- Existing Trees & Shrubs
- Proposed Specimen Trees & Shrubs
- Proposed Shrubs
- Proposed Hedge
- Proposed 1.8m c.b. Fence
- Grass
- Page Dividing Line

Climber
6 no Parthenocissus quinquefolia
750mm cs

22no Cornus alba 'Elegantissima' @ 750mm cs

13 no. Viburnum opulus @ 750 cs

39 no. Viburnum opulus @ 750 cs

REVISIONS
B 6/01 PLOT 22 PLANTING TO W.S REMOVED
A 5/00 Plot 14 & 15 planting reduced as per visibility splay

Allison Homes

Planting Layout — Plot 2 Cowbit

Scale 1:200 — December 1999

Dwg No.: 233/75/SHG5 A

DRAWING ISSUED 26 MAY

Town & Country Planning
Ecology
Landscape Architecture
Robert Doughty Consultancy
32 High Street, Helpringham, Sleaford NG34 ORA
Tel. (01529) 421646 Fax: (01529) 421358

STONE GATE

14no. Plants
Refer: Native Hedge Mix
(3 Plants per M.)

90no. Plants
Refer: Native Hedge Mix
(3 Plants per M.)

72no. Plants
Refer: Native Hedge Mix
(3 Plants per M.)

12no. Plants
Refer: Native Hedge Mix
(3 Plants per M.)

51no. Plants
Refer: Native Hedge Mix
(3 Plants per M.)

24no. Plants
Refer: Native Hedge Mix
(3 Plants per M.)

1 no. Parthenocissus quinquefolia

1 no. Parthenocissus quinquefolia

9no. Lonicera pileata @ 750mm c/s

24no. Cornus alba 'Elegantissima' @ 750mm c/s

108 no. Vinca minor alba @ 300 c/s

1 no. Parthenocissus quinquefolia

PUMPING STATION

(Refer to other sheet for planting details)

Qty.	Species	Size	Specification
	TREES		
4	Betula pendula	175-200	10L Container Grown
5	Crataegus laevigata 'Plena'	8-10	Standard
11	Prunus avium 'Plena'	8-10	Standard
4	Malus tschonskii	8-10	Standard
1	Sorbus aricuparia 'Asplenifolia'	10-12	Selected Std
	SPECIMEN SHRUBS		
9	Amelanchier canadensis	80-100cm	10L Container Grown
4	Cornus sanguinea	60-80cm	10L Container Grown
9	Cotoneaster lacteus	60-80cm	10L Container Grown
3	Ilex x altaclerensis Golden King	80-100cm	10L Container Grown
5	Pyracantha 'Orange Glow'	80-100cm	10L Container Grown
	CLIMBERS		
3	Parthenocissus quinquefolia	100-150cm	10L Container Grown

Qty.	Species	Size	Specification
	HEDGING PLANTS		
184	Crataegus monogyna	60-80cm	3yr Transplant
39	Cornus alba	40-60cm	2L Container Grown
26	Corylus avellana	60-80cm	O.G.
14	Viburnum opulus	60-80cm	O.G.
	SHRUBS		
24	Cornus alba 'Elegantissima'	80-100cm	10L Container Grown
9	Lonicera pileata	40-60cm	5L Container Grown
108	Vinca minor alba	30-40cm	2L Container Grown
	SHRUB BOUNDARY		
5	Corylus avellana	60-80cm	O.G.
2	Cornus sanguinea	40-60cm	2L Container Grown
5	Cotoneaster simonsii	40-60cm	2L Container Grown

NATIVE HEDGE for sheet 1
3 plants per metre (Double staggered row)

Species:	Size:	Height:	Plant %:	No's:
Crataegus monogyna	Transplant 3yrs	60-80cm	70	168
Cornus alba	2L	60-80cm	15	23
Corylus avellana	O.G.	60-80cm	10	15
Viburnum opulus	O.G.	60-80cm	5	8

Key:

- Existing Trees & Shrubs
- Proposed Specimen Trees & Shrubs
- Proposed Shrubs
- Proposed Hedge
- Proposed 1.8m c.b. Fence
- Grass
- Page Division Line

Allison Homes

Planting Layout

A Plot 62 front landscaping revised 8/11/00

Plot 2 Cowbit

Scale 1:200 December 1999

Dwg No.: 233/75/SHG4

Town & Country Planning
Ecology
Landscape Architecture
Robert Doughty Consultancy
32 High Street, Helpringham, Sleaford, NG34 0RA
Tel: (01529) 421646 Fax: (01529) 421678