

Do NOT scale from this drawing.
This drawing is copyright and may not be altered, traced, or used for any purpose other than that for which it is issued without written permission from the copyright holder.
The Contractor is to check all dimensions on site and report discrepancies to the designer prior to commencing work.
All details shown on this drawing are based upon typical site conditions. No responsibility can be accepted for abnormal conditions unless reported to the designer, so that amendments may be considered.
All works and materials used are to be in accordance with current British Standards, Agreement Certificates and Manufacturers instructions.
All Building Regulation inspections are to be carried out at the required stages.

REVISION NOTES;

-



Persicaria Affinis - Kabouter



Erica Carnea - Alpine Heath



Hebe Albicans



Fuchsia - Mrs Popple



Fagus Sylvatica - Beech



Fagus Sylvatica Purpurea - Purple Beech

Hedging			
Species Name	Abbreviation	Specification	Density
Fagus Sylvatica	FagSylv	120-150 (BR)	5m Staggered
Fagus sylvatica Purpurea	FagPurp	120-150 (BR)	5/m Staggered
Prunus laurocerasus Otto Luyken	Compact Laurel	25-30cm (BR)	5/m Staggered

Trees		
Species Name	Abbreviation	Specification
Betula pendula, alba	B-Pend	3m high, Standard, 8-10cm girth
Prunus Serrulata 'Amanogawa'	Pru'Amano	1.5-2m Feathered 15-20litre

Planting			
Species Name	Abbreviation	Specification	Density
Persicaria Affinis	Pers	9cm Pot	4/m Staggered
Erica Carnea 'Alpine Heath'	Erica	25-30cm 3L	3/m Staggered
Hebe Albicans	Hebe Alb	25-30cm 3L	3/m Staggered
Fuchsia 'Mrs Popple'	Popple	25-30cm 3L	3/m Staggered

NOTES:

- All planting & landscape operations to comply with Landscape Specification, BS4482(1989) 'Recommendations for General Landscape Operations' and BS3936 Pt 1 (1992) 'Specification for Nursery Stock Trees and Shrubs'. All container sizes shown are minimums acceptable - all plants to be supplied to sizes indicated.
- All ornamental shrubs to be planted at regular spacings in rows set diagonally to the edge of the bed.
- All ornamental shrub beds and hedges to be provided with coarse grade bark mulch minimum 75mm deep.
- Topsoil to be at least 450mm deep in all shrub areas, 100mm deep in all grass areas. Tree pits to be 750 x 750 x 500mm filled with topsoil.
- Provide 150mm wide gravel margin with timber edge, where grass abuts building. 100mm deep, laid on Terram.

IMPLEMENTATION
Landscaping work to be undertaken in the first planting season following completion of the building works.

0 1 2 5 10
Scale 1:100

seven22 ARCHITECTURE LTD

22 SHORE VIEW, PETERBOROUGH
CAMBRIDGESHIRE, PE7 8FS
E.info@seven22.co.uk - T.07799 585277

PROJECT
RESIDENTIAL DEVELOPMENT
128 BARRIER BANK
COWBIT
SPALDING
LINCOLNSHIRE PE12 6AL

SH SCENIC HOMES

CLIENT
SCENIC HOMES

TITLE
PROPOSED TREE & PLANTING SCHEDULES

DRAWING No.
089 - SP - 05

SCALE	DATE	REV
1:100 @ A1, 1:200 @ A3	NOV 24	