Scale 1:50 -in metres

0 1 2 3 4 5

N

Existing window to be removed and opening reshaped to provide new 'french' door opening

890 1585

2661

3647

2500

Proposed Study

Existing Bedroom

Proposed 550mm x 980mm Velux type GGL rooflight and light shaft to provide light to corridor at ground floor level

Proposed Dining Room

Existing door removed and opening infilled

1700

Form new opening through the existing wall

925

910

2054

Proposed Bathroom

2070

Reshaped Kitchen

2748

2183

Proposed Utility

Existing window to be removed and opening reshaped to provide new door opening

Form new opneing and doorset into the new utility

Section A-A

Up

New stairs

Section A-A

Existing door to be removed and opening blocked up

Provide new doorset

6500

Up

Reshaped Lounge

Existing window removed, opening resized and new doorset added

440 225 675 1640

2333

1350

1050

Proposed Porch

665 910 665

DETERMINED PLAN

JHDC Planning & Development

12 MAR 2009

Ref: 0179/09

Important Note
The builder is to check all dimensions prior to construction and any discrepancies to be reported to VINNARRY. Any existing walls must be checked prior to construction to prove suitability of any existing lintels and foundations which are to take any additional loadings.

Drawings produced by

Vinnarry

Property Design Solutions Ltd

01395 26-66-66

REVISIONS.		
NO.	DETAILS.	DATE.
	Revision A 1. Setting out and general arrangement amended following clients comments	

CONTRACT.
Proposed Extension and Alterations to;
2 Eastlands
Crowland

CLIENT.
Mrs and Mrs Annibal
2 Eastlands
Crowland

DETAIL.
PROPOSED GROUND FLOOR PLAN
(Project 09/1515)

DRAWN. Dean | DATE. 30 Jan 09

REVISION. A | SCALE. 1:50

STATUS. FOR APPROVAL

DRAWING NO.
Drawing 2