

NOTES

PROTECTION OF EXISTING VEGETATION

Existing vegetation to be retained on site shall be protected where necessary during works by a tree protective barrier, secured to a scaffold tubing framework with fluorescent tape to the top rail. Protective fencing shall be erected on the canopy drip line wherever possible. Laminated, waterproof A4 signs shall be fixed to the fence posts at 10m intervals bearing the words 'PROTECTED TREE ZONE - NO STORAGE OR OPERATIONS WITHIN FENCED AREA'.

Tracking of machinery, storage of chemicals and building materials shall not be permitted within the protected area. Leaks or spills should be removed immediately and the contaminated soil replaced. No bonfires shall be lit within 5m of the canopy spread. Any excavation work beneath the canopy spread shall be carried out by hand. All works affecting trees within the development shall be subject to BS 5837:2012.

TREE PLANTING

Trees will be planted at selected focal points to the front gardens of selected plots will break up the hard lines of the buildings and create focal points within the development. The tree species selected will maximise food and nectar sources for birds and invertebrates. Trees will be planted as Select and Heavy Standards to provide a reasonable degree of instant maturity to the development. Foundation design of new buildings shall accommodate proposed tree planting in accordance with NHBC guidelines.

Suggested species (but not exhaustive):

- Acer campestre (Ac)

Acer rubrum (Ar)

Betula pendula (Bp)

Betula utilis var. Jacquemontii (Bu)
- Carpinus betulus 'Frans Fontaine' (ChFF)

Prunus avium 'Plena' (Pap)

Pyrus calleryana 'Chanticleer' (PcC)

Sorbus aria 'Lutescens' (Sal)

SHRUB PLANTING

A mix of evergreen and deciduous shrubs will be planted in selected front gardens to soften the development and to provide a valuable food source for birds and invertebrates. A mix of medium/low shrubs will be planted to shrub beds with medium/large varieties used against high walls and hedges

Suggested species: () density/m2

Berberis candidula 'Amstelveen' (5), Berberis thunbergii 'Atropurpurea Nana' (6), Ceanothus thyrsiflorus repens (5), Choisya ternata 'Sundance' (4), Cotoneaster conspicuus 'Deconus' (4), Cyrtus praecox 'Albus' (4), Eunymnus fortunei 'Emerald n' Gold' (6), Fuchsia 'Mrs Popple' (4), Hebe 'Red Edge' (5), Hebe 'Autumn Glory' (4), Hebe 'Mrs Winder' (4), Hypericum moserianum (5), Lavandula angustifolia 'Hidcote' (6), Lavandula angustifolia 'Munstead' (6), Lonicera plicata (5), Philadelphus 'Mantlau d'hermire' (3), Prunus laurocerasus 'Low n' Green' (4), Rosa 'Swany' (4), Sarcococca confusa (5), Spiraea japonica 'Goldflame' (4), Viburnum davidii (5).

PUBLIC OPEN SPACE

A native hedgerow will be planted along the western edge of the open space to separate it from the adjacent properties and to increase the biodiversity value of the area. The basin will be sown with a wildflower seed mix to further increase the wildlife benefit of the open space.

Rev.A: Removal of 4 existing trees within pumping station easement and minor amends to accord with planning layout DD1T (SP) Aug 19



KEY

- Existing trees to be retained with RPA shown in orange

Existing trees to be removed.

Proposed Extra heavy standard (14-16cm girth) tree

Proposed heavy standard (12-14cm girth) tree

Proposed selected standard (10-12cm girth) tree

Proposed native hedge

Proposed mixed native species tree & shrub planting

Proposed ornamental shrub planting

Proposed turf
- Proposed amenity grass seed

Proposed wildflower grass seed

9m IDB Easement

Proposed 1800mm high close boarded timber fencing (detailed by others)

Sue Farmer BA MAUD MUI
Landscape Architect

fdalandscape

Westleigh Hall
Wakenfield Road
Derby Dale
Huddersfield HD8 8QJ
telephone 01484 865631
fax 01484 865616
iscdn 01484 866900
email info@fdalandscape.co.uk
www.fdalandscape.co.uk

client	Partner Construction		
project	Residential Development CREASE DRIVE, CROWLANDS, PETERBOROUGH		
drawing title	LANDSCAPE MASTERPLAN		
scale	1:500	date Jun 14	drawn by EW
	@A2		R/2244/1A