

Calculated by: Laura Birkin

Site name: Crease Drove, Fincham

Site location: Crowland

Site coordinates

Latitude: 52.66857° N

Longitude: 0.17215° W

This is an estimation of the storage volume requirements that are needed to meet normal best practice criteria in line with Environment Agency guidance "Preliminary rainfall runoff management for developments", W5-074/A/TR1/1 rev. E (2012) and the SuDS Manual, C753 (Ciria, 2015). It is not to be used for detailed design of drainage systems. It is recommended that hydraulic modelling software is used to calculate volume requirements and design details before finalising the drainage scheme.

Reference: 6370043

Date: 2018-05-31T21:34:57

Methodology

IH124

Site characteristics

Total site area (ha)	1.5
Significant public open space (ha)	.3
Area positively drained (ha)	1.2
Pervious area contribution (%)	0
Impermeable area (ha)	.98
Percentage of drained area that is impermeable (%)	82
Impervious area drained via infiltration (ha)	0
Return period for infiltration system design (year)	10
Impervious area drained to rainwater harvesting systems (ha)	0
Return period for rainwater harvesting system design (year)	10
Compliance factor for rainwater harvesting system design (%)	66
Net site area for storage volume design (ha)	1.2
Net impermeable area for storage volume design (ha)	0.98

* Where rainwater harvesting or infiltration has been used for managing surface water runoff such that the effective impermeable area is less than 50 % of the 'area positively drained', the 'net site area' and the estimates of Qbar and other flow rates will have been reduced accordingly.

Design criteria

Volume control approach	Use long term storage	
	Default	Edited
Climate change allowance factor	1.4	1.4
Urban creep allowance factor	1.1	1.1
Interception rainfall depth (mm)	5	5
Minimum flow rate (l/s)	5	5
Qbar estimation method	Calculate from SPR and SAAR	
SPR estimation method	Calculate from SOIL type	
	Default	Edited
Qbar total site area (l/s)	2.08	--
SOIL type	2	2
HOST class	N/A	N/A
SPR	0.3	0.3

Hydrology

	Default	Edited
SAAR (mm)	554	554
M5-60 Rainfall Depth (mm)	20	20
'r' Ratio M5-60/M5-2 day	0.4	0.4
Rainfall 100 yrs 6 hrs	63	
Rainfall 100 yrs 12 hrs	96.25	
FEH/FSR conversion factor	1.25	1.25
Hydrological region	5	
Growth curve factor: 1 year	0.87	0.87
Growth curve factor: 10 year	1.65	1.65
Growth curve factor: 30 year	2.45	2.45
Growth curve factor: 100 year	3.56	3.56

Site discharge rates

	Default	Edited
Qbar total site area (l/s)	2.08	2.08
Qbar net site area (l/s)	1.66	1.66
1 in 1 year (l/s)	5	5
1 in 30 years (l/s)	5	5
1 in 100 years (l/s)	5.9	5.9

Estimated storage volumes

	Default	Edited
Interception storage (m³)	39	39
Attenuation storage (m³)	919	919
Long term storage (m³)	0	0
Treatment storage (m³)	118	118
Total storage (excluding treatment) (m³)	958	958