52	Open area	Trees/bushes	Remove and dig trial hole to asses damage to adjacent foundations.	
53	Internal Timber – floors, supports etc	Significant evidence of woodworm and as such it is recommended that all aspects of the new design regarding floors etc that exhibit significant exposure to woodworm be removed and replaced with new timber sympathetic to original timbers.	Where original timbers are to be retained it is suggested that an authorised specialist contractor carry out extensive treatments to prevent further infestation.	