

1. All dimensions are in metres unless otherwise stated.
2. All levels are in metres.
3. This drawing is to be read in conjunction with all relevant Engineers and Architect's drawings, Specifications, Reports and Engineering Details.
4. Do not scale from this drawing.

Due to High Groundwater Table encountered there are potential issues with ingress of water within trenches. This can cause instability and collapse. Groundworker to ensure appropriate trench shoring up and de-watering works.

Due to the presence of organic soils designed levels have been kept to less than 1.3m build up to reduce the chance of settlement.

**Ground reinforcement required where CBRs less than 2%.
To be designed by a specialist.**

