



HIGH GROUNDWATER AND TRENCH INSTABILITY

Due to High Groundwater Table encountered there are potential issues with ingress of water within trenches. This can cause instability and collapse. Groundworker to ensure appropriate trench shoring up and de-watering works.



LOW STRENGTH ORGANIC SOILS

Due to the presence of organic soils designed levels have been kept to less than 1.3m build up to reduce the chance of settlement.

Buried services should be designed with flexible joints to allow the uptake of future movement cause by settlement of the soft soils beneath the site.

Ground reinforcement required where CBRs less than 2%. To be designed by a specialist.

General Notes

1. All dimensions are in metres unless otherwise stated.
2. All levels are in metres.
3. This drawing is to be read in conjunction with all relevant Engineers and Architect's drawings, Specifications, Reports and Engineering Details.
4. Do not scale from this drawing.

Drawing Key

- Site boundary - Taken from latest site layout referenced
- Half batter kerb (110mm upstand)
- Bullnosed kerb (25mm Upstand)
- Bullnosed kerb (6mm Upstand)
- Dropper kerb (110mm -25mm)
- Dropper kerb (110mm - 6 mm)
- Transitional Kerb
- Footway edging

Health, safety & the environment

In accordance with the Construction (Design and Management) Regulations 2015, the designs and details on this drawing have been the subject of a Designers Risk Assessment, to identify risks in the construction, use, or demolition of the scheme.

It is not considered necessary for Designers to highlight obvious and/or common risks (such as deep excavations, manual handling and working around heavy plant) which Contractors should be familiar with, and be able to control by good management and site practice.

So far as is reasonably practicable, the risks inherent in the design have been eliminated. Where it has been considered that elimination of a risk (or part of a risk) is not reasonably practicable, it has been reduced.

Significant unusual residual risks are identified on the drawing by use of a Yellow Caution Marker, beside the measures which have been adopted to eliminate and/or reduce them.

Refer to JPP Drawing No. 100 for Health & Safety Risks

This drawing has been based/developed using the following external drawings					
Type	Company	Drawing date	Drawing title	Date received	Rev
Topographical Survey	TCS Topo & Volumetric Surveys	Jul 2015	Topographical Survey July 2015	09.04.19	-
Topographical Survey	JPP	June 2020	XREF_Top (shows foul outfall MH 6701)	08.06.20	-
Site Layout	RGP	08.09.20	100-220/(90)001G External Works	28.01.21	G

JPP CONSULTING TO BE INFORMED IMMEDIATELY IF THESE DRAWINGS ARE NO LONGER CURRENT

Agreement	Approval Date
Section 278 (Works within the Existing Highway)	N/A
Section 38 (Highways adoption agreement)	Not Approved
Section 104 (Sewer adoption agreement)	Not Approved
Section 106 (Permission to discharge to public sewer)	Not Approved
Section 23 (Permission to discharge into watercourse)	Consent granted 09.04.20

DRAWINGS HAVE NOT BEEN APPROVED, UNTIL THE DRAWINGS ARE APPROVED THE DESIGNS AND DETAILS SHOWN ON THIS DRAWING ARE SUBJECT TO CHANGE
ANY WORKS UNDERTAKEN PRIOR TO TECHNICAL APPROVAL IS ENTIRELY AT THE CONTRACTOR'S RISK

THE SPECIFICATION IN ALL RESPECTS SHALL BE IN ACCORDANCE WITH THE CURRENT "LINCOLNSHIRE DEVELOPMENT ROADS & SUSTAINABLE DRAINAGE DESIGN GUIDE" AND "DEVELOPMENT ROAD AND SUSTAINABLE DRAINAGE SPECIFICATION AND CONSTRUCTION" PUBLICATIONS IN FORCE IN THE COUNTY AT THE TIME OF CONSTRUCTION.

- Rev

E

Drawing status updated to construction issue
- Rev

D

Section 38 note added to drawing key. Kerbing to plots 29-38 shared private drive removed from drawing key.
- Rev

C

Drawing revised to suit client comments
- Rev

B

Drawing revised following updated to road layout.
- Rev

A

Added a note regarding dropped kerbs for pump station access.

- By

RF

Checked

TH

04.02.2021
- By

SF

Checked

RF

10.12.2020
- By

RF

Checked

TH

03.11.2020
- By

MK

Checked

TH

25.09.2020
- By

IH

Checked

ML

26.03.2020



Northampton
4 Ironstone Way, Brixworth,
Northampton NN6 9UD
T: 01604 781811



Manchester
3rd Floor, 82 King Street,
Manchester, M2 4WQ
T: 0161 6822927



Milton Keynes
Suite 25 Unford Forum, Rockingham Drive,
Unford Wood, Milton Keynes, MK14 6LY
T: 01508 889433

E: mail@jppuk.net
W: jppuk.net

- Infrastructure Design

• Structural Engineering

• Planning Services
- Geotechnical & Environmental

• Surveying

• Professional Advice

Drawn By:	IH	Client	Geda Construction		
Chkd By:	ML	Project	Housing Development Crease Drove Crowland Kerbing Layout		
Scale @ A1:	1:500	Title			
Date:	March 2020				
Status:	CONSTRUCTION				
Project No.:	11557H	Drawing No:	120	Rev:	E

