

Do not scale off this drawing.
All site dimensions to be checked
before work commences.

Window & external door:

New window and door to rear elevation to be standard timber with double glazing and double glazing. Safety glass used in door to be 6mm. Small double vent to toilet to provide 600mm vent. Rear door to be fully glazed. Door to be 1800mm high and 800mm wide. Door frame and window frame to have paint finish.

Generally all retained windows/doors throughout to be repaired where required and finished with gloss paint throughout.

Install new 125mm hr. UPVC gutter connected to existing downpipe to rear elevation. Existing gutters and downpipes to be repaired/replaced where required.

Demolish existing outbuilding but retain existing boundary wall and parts of wall to form pier. Replace new brick on edge coping to wall and repair wall where needed.

Also demolish existing toilet and seal off redundant walls to provide fair faced brick finish repointed where required.

Adapt existing inspection chamber to allow for attached connection.

After existing rear wall of former shower room/entry to install new door and window openings replacing existing.

Drainage: (WC & Kitchen)

Install new 100mm dia UPVC pipe with rodding point at base all within duct (vented).

New pipe to be connected to existing inspection chamber with 100mm dia UPVC drain. Down to be protected where it passes through wall with precast concrete slab with 50mm clearance around pipe and protection from vermin entry. Drain to be protected by concrete paving.

Install down dia. polypropylene waste serving sink unit and washing machine and 50mm dia. serving wash drain. Sink unit waste to be 50mm dia. fittings to have 100mm deep seal traps.

Install new stud partition forming WC framed of 50mm dia. down dia. clad both sides with 12.5mm plasterboard.

Remove wall forming existing pantry.

Install extract fan to kitchen through existing opening to provide 60 litres per second extract.

Install small window opening in brickwork fully vented to existing and to match existing.

Install throughout ground floor chemical injection damp course below floor with 100mm plaster all to specialist installers specification.

Install new inspection chamber on existing drain run with a 100mm dia. vent stack. Size to be agreed with local authority and is the responsibility of the local authority.

Drainage: (Serving new bathroom)

Install new 100mm dia. soil and vent stack with rodding point at base all within duct. New pipe to be connected to new inspection chamber with 100mm dia. UPVC drain. Down to be protected where it passes through wall with precast concrete slab with 50mm clearance around pipe and protection from vermin entry. Drain protected by paving and floor.

Install down dia. polypropylene waste serving bath and 50mm dia. serving wash drain with 50mm dia. fittings to have 100mm deep seal traps.

Remove existing fireplace and form arched recess. Seal off existing flue and provide suitable air brick ventilation to flue.

Install where indicated to external walls 50mm thick Gypoc thermal board installed to manufacturers recommendations.

Heating and hot water:

Install gas fired balanced flue wall mounted boiler. Flue to be terminated through rear wall of bathroom. Flue to be terminated with 100mm dia. UPVC pipe. New radiators to be fitted with thermostatic valves. All hot water pipework to be insulated with Armaflex or equivalent. New hot water cylinder to be 100 litre capacity factory insulated type (50mm thick) and to be fitted with cylinder coat.

Install gas and electric meter boxes through existing wall with plaster over timber framing behind to finish flush with existing internal wall.

Existing drop fittings to be removed from this area.

Retain existing front entrance door and low window to front elevation, repair as required.

Replace existing timber floor to living room/former shop with new floor formed of 50mm light grey reinforced concrete on 100mm dia. aggregate. Polythene separating membrane on 50mm thick grade 30 expanded polystyrene insulation on 100mm thick grade 30 concrete slab on 100mm dia. aggregate. Polythene separating membrane on 50mm thick hardcore well consolidated and bladed.

Dark brown stained timber weather-boarding

New brickwork to match existing

SIDE ELEVATION

REAR ELEVATION

SIDE ELEVATION

New roof construction:

Redland Gravelux interlocking concrete tiles colour terracotta installed to manufacturers instructions on 200mm x 100mm battens on 100mm x 100mm rafters on built up timber roof constructed of:

30x100 rafters and ceiling joists at 450mm c/c.
20x100 wall plates
20x100 timbers battens to existing wall at max 600mm c/c to support rafters and ceiling joists
Min 25x150 fascia board

All structural timber to be grade SC3 and marked F15 or F18.

Install code 4 lead flashing between top of roof and existing wall.

Line of existing corrugated fibrous cement finished roof

Install 30x50mm mild steel steps between new roof structure and existing walls at 1.0m c/c average with 100mm x 100mm timbers where at right angles but no girders under.

Roof void ventilation:

Install over fascia strip vent to provide 10,000mm² vent per metre. Also install roof tile vents at top of pitch to provide 5,000mm² vent per metre.

Roof insulation:

Install 2 layers of 100mm thick fibreglass quilt insulation with 1 layer between and 1 layer over ceiling joists with min 50mm vent gap over.

New ceiling formed of 50mm plasterboard with perimeter supported and 'arter' finish.

Lights to new openings to be precast concrete slab lights.

Remove existing door and frame to attic room and fill opening with 215mm brick to match existing brick face to be set back approx 15mm.

Code 4 lead stepped flashings to new roof.

Remove existing translucent roof and install new multi skin poly carbonate translucent sheet roof including patent support ribs.

New section of stud wall formed of timber weather boarding (stained dark brown) on breather membrane on 100mm x 100mm grade 30 studs with internal finish of 12.5mm plasterboard on vapour barrier insulation between studs to be 100mm thick fibreglass quilt.

Code 4 lead flashing to top of wall taken up behind weather boarding.

Remove existing stud wall.
Repoint existing concrete paving where new drain installed.

SECTION B-B


SECTION C-C

SECTION A-A

GROUND FLOOR

FIRST FLOOR

SECOND FLOOR



SOUTH HOLLAND DC
HOUSING & PLANNING
DETERMINED
PLAN
16 AUG 1999
Ref: 0823/99

Project PROPOSED ALTERATIONS TO EXISTING COTTAGE 13 EAST STREET, CROWLAND.	ALAN HORNSBY ARCHITECTURAL SERVICES 'Little Acre' Peak Hill, Cowbit, Spalding, Lincs. PE12 6AW Tel. Holbeach (01406) 380591
Client MRS F.M. THOMPSON.	Scale 1:50/1:100 Date Aug 99 Dr. no. 99/51/01

AM ADM 230