© Copyright Barron Design Ltd.



Grow Out Units:
Plastisol coated steel walls and roof (Colour: Olive Green RAL 6003)
For further details refer to Morspan drawings:
2022-Flogro-Grow-Plan
2022-Flogro-Grow-Elevations

Hatchery:
Plastisol coated steel walls and roof (Colour: Olive Green RAL6003)
For further details refer to Morspan drawings:
2022-Flogro-Hatchery-Plan
2022-Flogro-Hatchery-Elevations

Process Building:
Plastisol coated steel walls (Colour: Mushroom RAL9001)
Plastisol coated steel roof (Colour: Olive Green RAL6003)
For further details refer to BDL drawings:
P674.300 Floor Plan
P674.301 Roof Plan
P674.302 Elevations

Storage Buildings:
Plastisol coated steel walls and roof (Colour: Olive Green)
For further details refer to BDL drawings:
P674.400 Plans
P674.401 Elevations

PV Panels:
All roofs to have PV panels (subject to confirmation by the specialist supplier).

Water Treatment:
Water treatment plant and equipment as LAT drawings:
LAT2500-GA-Typical

Sludge Tanks:
Polyester powder coated metal tanks (approx. 6m diameter x 3.0m high) - colour: Green RAL 6005.

Roads:
Primary access road to be bitmac to HGV specification;
Emergency access road to be pervious bitmac;
Service yard to be concrete to HGV specification;

Security fence:
Security fence to be 2.4m twin mesh security fence and posts (colour Green RAL 6005)

Landscaping:
Soft landscaping to be limited to grass seeding throughout.
Landscape screening to be provided along the main road boundary, including native tree and hedge planting.

Cycle shelters:
To be Broxap Apollo or similar (colour Green RAL 6005) with ebike charging points.

Electric Vehicles:
Charging points to be provided at 10% of all car parking spaces (ducts and infrastructure to be installed to all parking spaces for charging points to be expanded with demand).

Vehicle Barrier:
To be Barriers Direct Lockable manual arm barrier.

Revision				
P3	Parking revised, landscaping indicated, RAL references added.	CB	KM	22.08.22 Prelim
P2	Planning Issue.	CB	KM	04.08.22 Prelim
P1	First issue of drawing.	CB	KM	13.06.22 Prelim

Barron Design
28 Cathedral Road, Cardiff, CF11 9LJ | 4 Oak Drive, Marford, LL12 8XT
www.barrondesign.co.uk | CIAT Chartered Practice No: F2683

Project
New Development at Decoy Farm
FloGro Systems Ltd.

Drawing Title
Ultimate Extent of Project at Year 7

Drawn By:	Checked By:	Date:	Scale:
CB	CB	13.06.22	1:1000 @ A1

Job No.:	Drawing No.:	Revision:
P674	200	P3