	Area A
Total	Main Canopy Species
58	Alnus glutinosa
78	Betula pendula
58	Fraxinus excelsior
58	Prunus avium
58	Quercus robur
58	Sorbus aria
20	Tilia cordata
388	Total no. canopy species
	Understorey Species
157	Acer campestre
157	Cornus sanguinea
237	Corylus avellana
632	Crataegus monogyna
78	Ilex aquifolium
157	Prunus spinosa
157	Sorbus aucuparia
1575	Total no. understorey species
1963	Total area A

	Species		
Total	Main Canopy Species	% mix	Height (cm)
203	Alnus glutinosa	15	80-100
272	Betula pendula	20	80-100
203	Fraxinus excelsior	15	80-100
203	Prunus avium	15	80-100
203	Quercus robur	15	80-100
203	Sorbus aria	15	80-100
69	Tilia cordata	5	80-100
1356	Total no. canopy species		
Total	Understorey Species (5463)	% mix	Height (cm)
546	Acer campestre	10	40-60
546	Cornus sanguinea	10	40-60
819	Corylus avellana	15	40-60
2188	Crataegus monogyna	40	40-60
272	Ilex aquifolium	5	40-60 (3LC)
546	Prunus spinosa	10	40-60
546	Sorbus aucuparia	10	40-60
5463	Total no. understorey species		
6819	Overall total no.		

Key

Proposed woodland planting

WOODLAND TREE PLANTING A
3560m2

WOODLAND TREE PLANTING B
8949m2

15m

5m

1.6m

2.2m

Drain

Track

Sluice

St James's Drain

EXISTING 3.0m HIGH EARTH BUND

NEW 3.0m HIGH EARTH BUND

	Area B
Total	Main Canopy Species
145	Alnus glutinosa
194	Betula pendula
145	Fraxinus excelsior
145	Prunus avium
145	Quercus robur
145	Sorbus aria
49	Tilia cordata
968	Total no. canopy species
	Understorey Species
389	Acer campestre
389	Cornus sanguinea
582	Corylus avellana
1556	Crataegus monogyna
194	Ilex aquifolium
389	Prunus spinosa
389	Sorbus aucuparia
3888	Total no. understorey species
4856	Total area B

N

Rev.	By	Notes	Date

rdc Robert Doughty Consultancy

32 High Street, Helpringham
Sleaford, Lincolnshire NG34 ORA

Tel: 01529 421646
Fax: 01529 421358
Email: admin@rdc-landplan.co.uk
Web: www.rdc-landplan.co.uk

Client: Organic Recycling LTD		
Project: Decoy Farm, Crowland		
Drawing title: Woodland planting plan		
Drawing No. 1021-1-PP01	Rev.	Drawn KG
Scale 1:2500@A2	Date 19/10/11	Checked

All measurements should be checked against on site conditions and any discrepancies should be brought to the attention of the Robert Doughty Consultancy.