




WESTERN ELEVATION




NORTHERN ELEVATION



EASTERN ELEVATION



SOUTHERN ELEVATION



POSITION OF CONCRETE FOUNDATIONS AND BRICK PIERS TO SUPPORT MAIN FLOOR TIMBERS

DRAINAGE TO SEPTIC TANK OR MINI TREATMENT PLANT

SCOTTISH BORDERS HOUSING & PLANNING
25 APR 2000
Ref: 0514/00

RAINWATER TO 6 NUMBER 1MTR X 1MTR X 1MTR GRAVEL SOAKAWAYS SITUATED BELOW EACH DOWN PIPE.

GLAZING TO DOORS LAMINATED GLASS OR APPROPRIATE ADHESIVE FILM TREATMENT.

TOP VISION PANELS TO INTERNAL NON GLAZED DOORS.

UNISEX / DISABLED STAFF TOILETS FITTED WITH EXTRACTOR FAN (operated with lights but with time delay)

ACCESS RAMP 1: 12 @ 1200mm WIDE

POST AND SHORT FENCE TO MARK OUTER EXTREMITY OF MAIN DOORS OPENING

EXIT SIGNS TO MAIN DOORS AND FIRE DOORS; EMERGENCY LIGHTING TO MAIN ROOM.

DRAINAGE TO SEPTIC TANK OR MINI TREATMENT PLANT TO BE INSTALLED TO MANUFACTURERS RECOMMENDATIONS


ACCESS PLATFORM FENCED ALL ROUND

BUILDING SUPPORTED ON CONCRETE FOUNDATION PADS 150mm BELOW GROUND LEVEL 750mm X 750mm X 500MM REINFORCED WITH 1 LAYER MESH SUPPORTING ENGINEERING BRICKS PIERS FILLED WITH LEANMIX AND CAPPED WITH HD PAVING SLAB.

1 :100

DETERMINED PLAN

PROPOSED CHANGE OF USE TO INCLUDE SALES OF CARAVANS, TENTS, CAMPING EQUIPMENT AND LEISURE EQUIPMENT WITH SITING OF A PORTABLE BUILDING AND ASSOCIATED PARKING NORTH OF POSTLAND ROAD CROWLAND



25 APR 2000
Ref: 0574/00

PROPOSED CHANGE OF USE TO INCLUDE SALES OF CARAVANS, TENTS, CAMPING EQUIPMENT AND LEISURE EQUIPMENT WITH SITING OF A PORTABLE BUILDING AND ASSOCIATED PARKING AREAS

DETERMINED PLAN