

Hard/Soft Landscaping - Planting Schedule

Six Penny Piece, Spalding

Planting Schedule

All landscaping works to be in accordance with BS4428 1989 - Code of Practice for general landscaping operations. All plant material to be supplied to BS3936, parts 1 – 10 and handled in accordance with Horticultural Trades Association's Code of Plant Handling booklet 1985. Trees to be planted in accordance with BS 5837 : 2012. 300mm depth of topsoil to planting and grass areas.

Planting Areas

P1 – *Berberis thunbergii atropurpurea* – 2 year old plants container grown - 2 ltr pot - height 600mm planted as single row @ 300mm spacings. Light pruning twice a year.

P2 - *Lonicera nitida 'Maigrun'* - Honeysuckle

2 year old plants - planted as bare rooted stock - height 400mm, planted in a single row @ 300mm spacings, protected by guards with 100mm mulch. To be trimmed several times each season to keep neat and under 600mm high.

P3 – *Betula jacquemonti 'silver shadow'* in multi stem form. Secured with a root anchor system. Low stems to be removed from the main trunk whilst young. Once established, lightly prune as necessary through seasons.

P4 – *Lavendula 'Hidcote'*, *Verbena bonariensis*, *Iris latifolia*, *Allium 'Purple sensation'*, *Agapanthus africanus 'Albus'*. Water regularly. *Lavendula* to be trimmed back in early April to keep neat. *Iris latifolia*, foliage to be removed once it has died down.

Remaining areas laid to grass