Five Bar Gate

Gravel Drive

Gravel Drive

Footpaths

Parking

Parking

Parking

Parking

Turning Area

Sewage Treatment Plant min. 7m away from dwelling, located within 30m of an access point.

Discharge to water course with agreement from Anglian Water or, drainage field system to be min. 10m from any watercourse, min. 15m from the building.

Exact location to be determined under Building Regulation application.

7000 mm

Soakaway min. 5m away from dwelling and min. 2.5m from any boundary. Designed and installed to Approved Document H3

Percolation Test

The following test was carried out three times with two seperate trial holes in the vacinity of the proposed location of soakways.

- a 300m² trial hole was excavated to a depth of 300mm below the proposed invert level of the distribution pipe.
- the trial hole was filled with min. 300mm of water and allowed to drain overnight.
- 24 hrs later the test holes were filled with water to a depth of 300mm, an observation of the time in seconds was recorded for the water to drain from 75% full to 25% full level i.e. a depth of 150mm.

Test Result

The average time from both trial holes was a seepage time of 12 seconds.

12 sec/150mm = 80Vp
Acceptable is between 12-100Vp ∴ ok.

Lawn

Electric Meter

S.V.P.

5000 mm

Existing entrance

Soakaway min. 5m away from dwelling and min. 2.5m from any boundary. Designed and installed to Approved Document H3

Existing trees and landscaping to front elevation to remain as much as possible.

Court Yard

Soakaway min. 5m away from dwelling and min. 2.5m from any boundary. Designed and installed to Approved Document H3

Soakaway min. 5m away from dwelling and min. 2.5m from any boundary. Designed and installed to Approved Document H3

5000 mm

Ramped Approach to comply with Approved Document M1 Access For All

New Access

5000 mm

Parking

Parking space to comply with Approved Document M1 Access For All

Parking

Refuse Storage

Existing trees to remain

3000 mm

Stock Post & fencing to match existing

Larch Bin Store

Conditions: 7-Soakaway, 8-Foul Water Disposal, 9-Landscaping , 10-Boundary Treatments & 16-Car Parking Plan

0m 1m 2m 3m 4m 5m

VISUAL SCALE 1:50 @ A1

0m 2m 4m 6m 8m 10m

VISUAL SCALE 1:100 @ A1

Rev	Description	Date

RICHARDS ARCHITECTURAL

RUALEN, MILL GREEN ROAD
PINCHBECK, SPALDING, LINCS PE11 3PU
07939 000 388

PROJECT

Discharge of Condtions to
Planning Application H03-0445-21

CLIENT

Mr and Mrs Avery
Lucksbridge Farm House
South Drove
Spalding PE11 3ED

DRAWING

Proposed Block Plan
Conditions 7, 8, 9,10 & 16

DRAWING NUMBER:	DATE:
RA/CC/1211/21/02	April 2022
DRAWN BY:	SCALE (@ A1):
RW	1 : 100

COPIES OF THESE DRAWINGS MUST NOT BE TAKEN, TRACED OR ALTERED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH THEY ARE ISSUED WITHOUT WRITTEN PERMISSION OF RICHARDS ARCHITECTURAL. THESE SERVICES ARE PRODUCED ONLY FOR THE PURPOSE OF OBTAINING PLANNING OR BUILDING REGULATIONS APPROVAL AND DO NOT CONTAIN A FULL SPECIFICATION FOR THE PROPOSED WORK AND MUST NOT BE USED AS A CONTRACT DOCUMENT ALONE.
THE PROPOSED WORK WILL NOT BE SUPERVISED/INSPECTED BY RICHARDS ARCHITECTURAL (unless agreed otherwise in writing by the client). THEREFORE IT IS THE CLIENT OR THEIR APPOINTED BUILDER/CONTRACTORS RESPONSIBILITY TO CONTROL WORKMANSHIP/MATERIALS AND SPECIFICATION AND ANY VARIATIONS TO THE CONTRACT. IT IS NEITHER PRACTICAL OR REASONABLE TO SHOW ALL THE RELEVANT MATTERS ON THE DRAWINGS, THE FACT THAT MATTERS ARE NOT MENTIONED DOES NOT ALEVIATE THE BUILDER/CONTRACTOR FROM RESPONSIBILITIES OF NON-COMPLIANCE IN CARRYING OUT THE WORK. ALL WORKS AND MATERIALS TO BE FITTED AND INSTALLED TO THE MANUFACTURERS INSTRUCTIONS AND COMPLY WITH THE MANUALS AND REQUIREMENTS OF THE CURRENT EDITIONS OF BUILDING REGULATIONS, BRITISH STANDARDS, CODES OF PRACTICE, BRITISH STANDARDS OR EUROPEAN CODE AS ALL.
MEASUREMENTS ON THIS DRAWING ARE NOT TO BE SCALED FOR CONSTRUCTION/ORDERING PURPOSED. ALL DIMENSIONS FOR SETTING OUT OF THE WORKS AS SHOWN ON THE DRAWING TO BE CHECKED BY THE BUILDER/CONTRACTOR PRIOR TO THE COMMENCEMENT OF WORK AND ANY DISCREPANCIES REPORTED IMMEDIATELY. WHERE APPLICABLE DIMENSIONS SHOWN ARE EITHER THE OUTSIDE/INSIDE OF trek OR brickwork AND NOT FINISHED PLASTER. IT IS RECOMMENDED THAT A SITE SOIL SURVEY IS UNDERTAKEN PRIOR TO COMMENCEMENT OF WORKS. THE ACTUAL POSITIONING OF APPARATUS MUST BE ESTABLISHED BY THE BUILDER/CONTRACTOR PRIOR TO COMMENCEMENT OF WORK AND REPOSITIONED TO SUIT THE INDIVIDUAL SERVICE SUPPLIERS INSTALLATION RECOMMENDATIONS.
RICHARDS ARCHITECTURAL WILL NOT SHARE ANY CONFIDENTIAL INFORMATION WITH OTHER PARTIES WITHOUT YOUR CONSENT. FOR A COPY OF OUR PRIVACY POLICY PLEASE CONTACT NIKKI@RICHARDSARCHITECTURAL.CO.UK

HEALTH & SAFETY
Be client is to ensure that the appointed contractor is familiar with and complies with Health & Safety for Building Sites and Work Places.