Copyright JKDS Ltd.

Do not scale drawings, except for Planning purposes, request any dimensions required.

Rev.	Date	Details
A	24.08.23	Utility window width and location

New 1600x1200 window located in line with existing bedroom window over.

New 1500x1050 h window located to provide min. 100mm to larch cladding.

700

Rehang door

Enlarge existing opening to retain 700mm masonry return. See notes and calculations for beam over.

UTILITY ROOM

SITTING ROOM

KITCHEN

Step up 240mm

500

Remove existing non-loadbearing walls and form storage cupboard to utility room.

TOILET

Re-site WC appliances as detailed in notes.

Remove existing non-loadbearing masonry nib.

BATHROOM

BEDROOM

New window 1200x1200 located in line with existing window over.

ENTRANCE LOBBY

partner LABC

Client:	Proposal:	Scale @ A3	Title
MR. P. GARFORD	LAYOUT AND FENESTRATION ALTERATIONS AT 14 STOWEGATE, DEEPING ST. JAMES, PETERBOROUGH	1 : 50	PROPOSED PART GROUND FLOOR LAYOUT 1
		Dwg No. 23. 3505. 03	

JANICE KENDRICK DESIGN SERVICES e-mail- jkds@talk21.com tel : 07711 007209