







02 ELEVATION A




03 ELEVATION B



01 P L A N



04 ELEVATION C



05 ELEVATION D

- Carefully repair existing wall finish and make good existing plaster where necessary - paint finish.
- Carefully remove timber board covering and remove contents. Walls to be repaired and made good, paint finish.
- Exposed Timber beams to be cleaned and repaired, left exposed.
- Existing window to be stripped, repaired and repainted.
- Ironmongery and sliding sash gear to be replaced if damaged.
- Existing door to be carefully removed and replaced with a 5 plank door to match existing.
- Existing radiator to be carefully removed & replaced. Wall to be repaired.
- Existing faux flooring to be carefully removed, Timber boards to be carefully stripped, repaired, re-laid and left exposed.
- Existing Skirting board to be carefully removed, stripped, re-laid and made good, with additional proposed skirting to match existing, paint finish.
- Existing mini cable trunking and sockets to be carefully removed, walls to be made good, paint finish.
- Electrical services to be replaced - TBC.
- Existing plastic pipe work to be carefully removed, wall to be repaired and made good. Paint finish.
- Existing sink to be carefully removed, walls to be repaired and made good. Paint finish.
- Proposed Conservation Roof Light Window.
- Existing wall to be carefully opened to create an access door to RM.19. Proposed door to match existing. Walls to be repaired and made good. Paint finish.
- Proposed new stud wall partition with a new access door to en-suite. Paint finish.
- Proposed new door to match existing.
- Secondary glazing to be fitted internally for thermal efficiency.

Note: Remedial works as per CARE Engineers drawings.

Issued for Planning 11.01.2023 00
Issued for Information 16.11.2022 00
Issue - Amendment Date Rev

Project Wykes Manor, Wykes Ln, Donington, Spalding, PE11 4SD

JONATHAN HENDRY ARCHITECTS LTD
10 Nickerson Way
Peascliffe Business Park
Hullonder Clay
Uncolnshire
DN33 5HS

T: 01522 458100
W: www.jonathanhendryarchitects.com

Subject Proposed Internal Elevations - RM.17

Scale 1:25 Date 11.03.2022

Original Size A1

Drawing No. GA_RM.17 00