Proposed pruning work and maintenance of Donington Church trees.

Trees No. 16 – 24 Pollard to I/3 approx. above existing pollard knot removing any other dead or diseased branches to promote a healthy recovery of the tree. Special note being taken of trees 16 – 19 inc. as they are slightly higher. Every effort will be made to ensure the future health of the trees is taken into consideration.

Trees No. 1 – 7 Pollard to 1/3 approx. above existing pollard knot removing any other dead or diseased branches to promote a healthy recovery of the tree. Tree No.7 to be stripped of Ivy and assessed to whether it would blend in with trees 8 – 14. All work done with the attention of promoting the future health of the trees.

Trees No. 8 – 14 Reduce crown by 25% and remove any deadwood and branches that dangerously overhang. Every effort will be taken to ensure the natural shape of the tree continues to thrive.

Tree No. 15 Pollard to healthy wood to make it safe as an attempt to save the tree from felling. If this attempt fails then we would have remove the tree in the future.

PLAN 1

~ St. Mary and the Holy Rood. ~

— Donington. —

— Lincolnshire. —

