

Electricity Meter Boxes

MCL's Mitras™ Meter Box range is the largest and most comprehensive available in the UK and Ireland. MCL manufacture and supply electricity meter boxes to BS8567:2012 Specification for outdoor electricity meter cupboards. Our meter boxes are approved and installed by all major utility companies and house builders.

The most commonly used model for new house builds, the recessed electricity meter boxes house all domestic electricity meters with a larger version available for 3-phase supply. A Slimline version is available for where wall space is restricted, a shallow version used mainly for timber framed buildings, a 'fire-retardant' version and an ESB approved version for use in the Republic of Ireland. The easiest to install, the surface mounted electricity meter boxes are suitable for domestic electricity meters, with a larger version for 3-phase meter installations.

Mitras™ Recessed Electricity Meter Box

Model Number: M01023 (EB1)

Known also as model M01026 by our stockists, the most popular electric meter box, the standard recessed electric meter box houses any domestic electric meter and is designed to mirror the standard recessed gas meter box. With a variety of cable entry positions, this universal version can be used in any area of the UK (except Manweb area). Complies with BS8567:2012 Specification for outdoor electricity meter cupboards. Fire retardant version M02025 is available from our stockists.



Mitras™ Brown Recessed Electricity Meter Box

Model Number: M01126 (EB1)

Overall size (mm): 409 W x 595 H x 210 D

Brickwork opening (mm): 365 W x 535 H x 150 D

Manufactured in a milk chocolate brown colour, this version of the standard recessed electric meter box is less obtrusive against red brickwork than the standard white box. Built to the same specification as the universal version M01023, this meter box can be used in any area of the UK. Hockey stick only available in white or black, available from our stockists. Replacement door is the M00041. Complies with BS8567:2012 Specification for outdoor electricity meter cupboards.



Mitras™ Medium Manweb Recessed Electricity Meter Box

Model Number: M35047 (EB2)

Overall size (mm): 485 W x 685 H x 210 D

Brickwork opening (mm): 405 W x 610 H x 150 D

Larger than the standard box, as usually required in the Manweb electricity area and used in Northern Ireland, the Medium recessed electric meter box houses any domestic electric meter. Cable entry can only be through the building cavity as the external protrusion is smaller than the standard box. Complies with BS8567:2012 Specification for outdoor electricity meter cupboards.

