





Ground Floor




First Floor




South Elevation



East Elevation



North Elevation



West Elevation

DETERMINED PLAN

SHDC PLANNING & DEVELOPMENT
27 APR 2006
Ref. 0583/06

MATERIALS SCHEDULE

Roof: existing pantiles carefully removed and set aside for reuse, any rotten or infested tombers renewed, roof insulated, felted and battened, prior to refixing original tiles. [NOTE: good clay pantiles from demolished sections to be used as spares to make good any shortfall from re-roofed sections.]

External Walls: existing walls to bew raked out and repointed in lime mortar, replacing any decayed bricks. new walls to be constructed with matching bricks, salvaged from demolition of outbuildings.

Windows and doors: Timber framed sash and casement replacement windows - generally to existing pattern [sash or casement] in existing openings, unless otherwise noted. Windows made & supplied by Bereco to suit existing openings & to their standard conservation detailing. Glazed screens in barn door openings constructed to architects detail.

Rev C - Apr'2005 - windows & car port/store revised
Rev A - Apr'2005 - central chimney reinstated, notes revised

ROBERT LOWE CHARTERED ARCHITECT
1-2 North End, Swineshead
Boston, Lincs., PE20 3LR
Phone 01205-821117
Fax 01205-821139
info@lowe-architects.com

Project: Alterations and barn conversion
57 Days Lane, Donington
Spalding, Lincolnshire
Date: Dec'2005
Scale: 1: 100 @ A1
Client: Mr. & Mrs. J. Woodhead
Drawing Title: PROPOSED ALTERATIONS PLAN & ELEVATIONS
Project No: 05079
Drawn: RWL
Drawing No: 03
Rev: C

Contractors are to check all dimensions on site and to report any discrepancy to the Architect. Do not scale from the drawing.
© 2005