



TF 23 NW

DONINGTON

PARK LANE
(north side)

2/25

The Vicarage

G.V.

II

Vicarage. Early C19, altered mid and late C19. Red brick in English bond, painted ashlar dressings, slate roof. 2 gable stacks. 3 storey, 3 bay front with moulded eaves, cornice and paired barrel brackets. Central half glazed 8 panel door with fan decoration to lower panels and plain overlight, covered by late C19 brick porch with pilasters and dentillated cornice. 6 panel door and bordered overlight. To left a single canted bay with plain sashes, dentillated cornice, lead roof and to right a single glazing bar sash. To first floor 3 similar windows and to second floor 3 smaller similar windows. All windows have cambered rusticated splayed ashlar lintels.



TF 23 NW

DONINGTON

PARK LANE
(north side)

2/26

Stables at
the Vicarage

G.V.

II

Stables. Early C19. Red brick in Flemish bond, pantile roof. 2-storey, 3 bay front having central planked door in semi-circular surround with key and impost blocks. Flanked by single louvred light. To first floor are 2 smaller planked openings all with basket arches. Included for group value only.



TF 23 NW

DONINGTON

PARK LANE
(north side)

2/25

The Vicarage

G.V.

II

Vicarage. Early C19, altered mid and late C19. Red brick in English bond, painted ashlar dressings, slate roof. 2 gable stacks. 3 storey, 3 bay front with moulded eaves, cornice and paired barrel brackets. Central half glazed 8 panel door with fan decoration to lower panels and plain overlight, covered by late C19 brick porch with pilasters and dentillated cornice. 6 panel door and bordered overlight. To left a single canted bay with plain sashes, dentillated cornice, lead roof and to right a single glazing bar sash. To first floor 3 similar windows and to second floor 3 smaller similar windows. All windows have cambered rusticated splayed ashlar lintels.



TF 23 NW

DONINGTON

PARK LANE
(north side)

2/26

Stables at
the Vicarage

G.V.

II

Stables. Early C19. Red brick in Flemish bond, pantile roof. 2. storey, 3 bay front having central planked door in semi-circular surround with key and impost blocks. Flanked by single louvred light. To first floor are 2 smaller planked openings all with basket arches. Included for group value only.