


Floodlighting Area flood 7



AF7BA



AF7WGW



AF7SS




AF7BD



AF7LO

Spill shields
to be used.




AF7BD top




AF7BD side



AF7SS/LO top



AF7SS/LO side



AF7WGW/B top



AF7WGW side

Spares and Attachments

Description	Weight (kg)	Cat. No.
Single-ended lampholder		GL11
Double-ended lampholder		GL12
Bar door	1.1	AF7 B
Spill shield	1.2	AF7 C
Louvre	1.6	AF7 D
Baffle attachment (SON-T and MT70D lamps)	0.02	AF7 E
Baffle attachment (MQH-DL lamps)	0.02	AF7 F
Wire guard in white holder	0.6	AF7 G
Wire guard in black holder	0.6	AF7 H
Cage (455mm l x 465mm w x 509mm h)		AF7 I
White holder for filters	0.4	AF7 J
Black holder for filters	0.4	AF7 K
Red filter	0.4	AF7 L
Blue filter	0.4	AF7 M
Green filter	0.4	AF7 N
Yellow filter	0.4	AF7 O

Note: Filters and holders must be ordered separately.

DETERMINE
PLAN



380



Permitted mounting positions

High pressure sodium floodlight for general lighting, parks, industrial storage and loading areas, building facade security and sports lighting (especially tennis courts).

- 150W and 250W SON-T lamps for economy and
- 250W metal halide version also available
- GRP body requires no maintenance
- Toughened glass front
- Supplied with lamp
- Integral control gear
- Spill shield available for reduced glare
- Specular reflector available for narrow beam distribution
- Low glare version (OTLGB250.4) available for tennis and similar applications
- IP65 dust tight and jet proof
- Class I electrical
- BS4533.102.5

Materials/Finish

Body: White one-piece GRP moulding with integral control gear.

Lens: Toughened soda lime glass in GRP frame with four stainless steel swivel bolts and silicone rubber gasket.

Standard reflector: Dimpled anodised aluminium.

Strut: 5mm zinc plated and passivated steel with black coat paint finish.

Installation/Mounting

Cable entry by 20mm combination gland/cord grip for 10mm o/d cable. Three-way terminal block for 6mm² conductors.

Zone 2 hazardous area version also available. See page 14.

For special tennis floodlighting package see Tennis Floodlighting section, page 44.

Specification

To specify state:

Enclosed white GRP floodlight with toughened glass front and integral control gear for tubular SON lamp.

Mounted on adjustable steel strut. Sealed to IP65.

As Thorn Sonpak.

Ref: 087094

Light fittings.

434

DETERMINED
PLAN