



Proposed Site Plan - (scale 1:200)

LANDSCAPING - WORKS SPECIFICATION

All plants and planting to conform with all the relevant latest British Standards and Codes of Practice.

GENERAL

Ensure adequate suitable water is available for planting and subsequent maintenance. Maintain the planted areas until 12 months after the date for completion as follows:

- Hoe or otherwise remove weed.
- Make up levels where necessary with topsoil.
- Keep plants watered in hot weather early or later in the day.
- Spray against harmful insects or fungal attack.

TREE SPECIFICATION (14-16cm girth @ 1m from ground level)

LANDSCAPING - WORKS SPECIFICATION

All plants and planting to conform with all the relevant latest British Standards

TREE PLANTING

Excavate pit 1.25 x 1.25 x 600mm deep, fork subsoil and sides of pit, spread roots evenly and backfill with good quality topsoil, firming 150mm layers. Staking: Stakes to be 1.8m peeled pointed 'antialised' softwood, minimum top diameter 20/30mm. Tie: One approved tie, attached within 250mm of top of stake. Mulch: 50mm depth of coarse grade pulvenced bark or equivalent, spread over planting pit.

TREE SPECIFICATION

MJD MALUS JOHN DOWNIE
TT Tilia Tomentosa
CXM CRATAEGUS X MEDIA
SB SILVER BIRCH
CG CIDER GUB (EVERGREEN)
LN LAURUS NOBILIS (EVERGREEN)

ALL NEW TREE PLANTING TO BE
(14-16cm girth @ 1m from ground level)

HEDGE SPECIFICATION

mixed native hedge where indicated (600 - 900 high bare rooted transplants 350mm between plants in double staggered rows 500mm apart. Hedge to be 80% Hawthorn, 5% Hazel, 5% dog rose, 5% holly, 5% field maple

SOFFIT LIGHTING I.S. TO BE PROVIDED TO ALL FRONT GABLES AND UP AND DOWN LIGHTING IS TO BE PROVIDED ADJACENT TO FRONT DOORS AND GARAGES.

NOTE:
PLOTS 8, 9, 10 AND 11 WILL BE BUILT TO THE HIGHER ACCESS STANDARDS OF PART M4(2) OF THE BUILDING REGULATIONS

provide 900mm wide paving slabs to the perimeter of the dwelling with 150mm gravel strip to the inside

note:
all surface water drainage is to be safely conveyed and attenuated during storms up to and including the 1 in 100 year critical storm event.

All surface water and Rainwater drainage will discharge into soakaways or crates and this will be confirmed by way of a percolation test prior to Building Regulation submissions.

The Foul Drainage design will be so that it will discharge into ex. foul drain and this will be agreed by Building Control

this drawing is for planning purposes
and should only be used as a guide

Note: vehicle recharging points provided within all plots curtilage	Rev A	Acoustic fences/walls noted	13.01.22
	Revision	Amendment	Date

Client

Project
Proposed Residential Development
Land at Magnum Fabrications
High Street, Donington
Lincolnshire

Dwg Title

Proposed Site Plan

Dwg No.
202494-102

Scale
1:200

Date
08/22

Rick Smith Design
Architectural Design Consultancy

Ardent House, 18 Eastgate,
Sleaford, Lincolnshire NG34 7DP
Tel: 01529 414363 or 07786 838788
e-mail: rick@ricksmithdesign.com