

Holophane Europe Ltd offer a Lighting Design Service in good faith and without charge, every effort is made to ensure we interpret the design specification accurately.

All illuminance values shown are the result of theoretical computer calculations; summated by luminaires positioned in a fixed relationship to each other and the statistical zone.




In practice the values may vary due to tolerances in column installation, luminaire orientation, surface reflectance and fluctuations in power supply (voltage).

Results provided within this design are derived from product specific photometry, the substitution of alternative luminaires will not produce comparable results.

Statistics

Description	Symbol	Avg	Max	Min	Min/Avg
Car Park	+	16 lux	80 lux	5 lux	0.31
Service Yard	+	31 lux	74 lux	9 lux	0.29
spill		3 lux	75 lux	0 lux	0.00

Schedule

Symbol	Label	Image	Quantity	Manufacturer	Catalog Number	Description	Lamp	Lumens Per Lamp	Wattage	Plot	Notes
	A1		5	HOLOPHANE EUROPE LIMITED	DPL.1.LA073.FWBL.W049	Denver iD Post Top Fitting	LED C.7,000 Lumens	6534	49		
	EX		3	HOLOPHANE EUROPE LIMITED	DSX0.1.LA084.AY	EXISTING TRT STREETLIGHT	LED C.8000 Lumens	7802	64		
	A3		1	HOLOPHANE EUROPE LIMITED	DPL.1.LA063.SY.W048	Denver iD Post Top Fitting	LED C.6,000 Lumens	6006	48		
	B1		2	HOLOPHANE EUROPE LIMITED	DWL.1.LA043.FW.W025	Denver iD Wall	LED C.4,000 Lumens	3602	25	