

PACK SPECIFICATION 77766

2 OFF FRONT DOORS AND 2 OFF REAR
ACCESS PANELS

MINIMUM FRONT ACCESS REQUIRED

500mm

MINIMUM LEFT-HAND END ACCESS

REQUIRED 1000mm

MINIMUM RIGHT-HAND END ACCESS

REQUIRED 500mm

PLANT MAY BE PLACED AGAINST THE
WALL,

HOWEVER IT IS RECOMMENDATION TO
ALLOW MINIMUM 500mm TO ENHANCE
ACCESS FOR SERVICE AND
MAINTENANCE TEAM

1 X YBD36K1E-TFN

1 X YB45K1E-TFN

1 X 2CES-3Y-40S

TMU0.8-134CA-EC63.H1-A2L

WEIGHT: 1100kg (ESTIMATED).

NOISE RATING 30 dB(A) @ 10m
(FREE-FIELD)

DESIGN PRESSURE ($\leq 32^{\circ}\text{C}$)

HIGH SIDE 25 BAR

LOW SIDE 15 BAR

DESIGN PRESSURE ($\leq 38^{\circ}\text{C}$)

HIGH SIDE 29 BAR

LOW SIDE 18 BAR

5/8" PRV VENT LINE

5/8" LIQUID FEED CONNECTION

1.3/8" HT SUCTION RETURN

7/8" LT SUCTION RETURN

WARNING: PACK FOR USE WITH A2L REFRIGERANTS ONLY

CHANGE REVISION TABLE

ISSUE	CHANGE	DCN	DESIGNER	DATE
2	Control panel and electrics changed. Awning on right hand side changed.	1991	HB	02/11/2020
3	HT Suction Pipework changed to 1.3/8"		HB	15/01/2021

