existing trees at rear boundary to be retained and maintained

equal levels

equal levels



Brickwork to be Crest Old Saxon Blend

GROUND FLOOR LEVEL OF HOUSE TO BE 150 MM HIGHER THAN SITE LEVELS

existing 2m fence to be retained and maintained

Roof tiles to be Sandtoft Rustic Red Double Pantiles

existing 2m fence to be retained and maintained

Paving to be Quorndon Riven Buff

equal levels

equal levels

existing 2m fence to be retained and maintained

existing 900mm fence to be replaced to match existing fence.

acer campestre, 2m standard, container grown

Crataegus monogyna (Hawthorn) 450 mm centres - 300mm high on planting

equal levels

gravel driveway

laurel hedge, container grown in 3 litre containers and planted in double staggered rows at 450 mm centres

PLANTING AND AFTERCARE NOTES

All ground to be properly cultivated and tilthed prior to planting, and treated with slow release fertilser. Weeds and foreign material including large stones are to be removed from site.
All shrubs to be planted at centres specified and watered on completion
Trees to be planted In shallow plts with a layer of compost at the bottom, and are to be staked and tied with proprietary tles. The stakes are to be at least 600mm longer than the staked height of the tree to ensure that sufficient Is driven into the ground.
Bare ground within and around shrubs and trees to be covered with tree bark.
Shrubs and trees to be watered In dry perlods.
Any plants that die are to be replaced
Tree ties are to be replaced as necessary
All trees and shrubs are to be maintained for a five year period beginning with the date of completion of the scheme and, during that period, all losses shall be made good.

Revision	Date	Drawn	Description

Client Mr Harry Brown

Project Site adj. to 2 Greenfields, Holbeach

Drawing Condition Compliance (Conditions 3, 4, 5 & 6)

Scale 1:100 @ A2 Drawn AWM Checked TAC Date 17/09/2014

Drawing No. 14/390/PA/004

TAC ARCHITECTS

Trevor A Clay RIBA Ltd, 14 Old Fendike Road, Weston Hills, Spalding, Lincs. PE126DD
01406 380027 07778 597975 trevor@tacarchitects.co.uk www.tacarchitects.co.uk