

ULTIMATE ROSE MARK III UPVC SASH WINDOW

Manufacturer: SPICGEM Ltd (t/a Roseview windows)

Website: www.roseview.co.uk

Phone: 01234 712657

Email: info@roseview.co.uk

Key contact: Richard Burrells

MANUFACTURING DETAILS

Material profile:	Rehau extruded profiles (RAU PVC 1406) BSEN 12608:2003 Rehau kitemark: KM13358
Mullion sections:	85mm mullion (slim mullion for combination)
Meeting rail:	35mm mid rail (Standing Profiles)
Outer frame:	66mm face external
Cill section:	62mm x 25mm x 149mm (flush cill) 87mm x 50mm x 149mm (flush deep face cill) 62mm x 27mm x 225mm (projecting cill) > Cill projection of 225mm – 76mm
Sash horns:	Seamless run through or seamless no horn
Finishes:	White flat RAL 9016 White ash textured – RAL 9010 White Ultimatt smooth foil – RAL 9010 Cream ash – RAL 9001 Bespoke RAL colour – 1 face/2 face
Internal astragal bars:	22mm sculptured 559261-701 smooth white 589261 – 705 white foil

External astragal bars: 22mm chamfered

559251 – 701 smooth white

589251 - 705 white foil

Glazing gasket: Foamasil universal gasket – 235203 – 134 white

Weatherseal: Linear white 6.9 x 850 EC WF White 11190852

Linear white 6.9 x 850 EC WF Grey 11190851

Deep bottom rail gaskets: EPDM Front and Rear gaskets white 219350–005 & 219360- 005

Glazing beads: 28mm sculptured beading/low level co-extruded gasket

559600-701 smooth white

589600 – 134 white foiled

35mm midrail gasket: Reddiplex co-extruded wedge gasket R1128301

Trickle vent: Through head 1700/2700/4000/5000 XS13 Titon

Child restrictor: Mighton Angel vent lock

Shark fin restrictor

Rola limit stop

> 100mm/150mm/200mm

Balances: Caldwell Torso balances

Caldwell Ultra lift balances

Tilt restrictors: Caldwell quick release tilt restrictor – 250mm/350mm

Ironmongery: Authentic ERA globe range cam locks

Globe sash lifts

Globe tilt knobs

Globe pole eyes

> Chrome, Satin, Black, Bronze, Gold

Reinforcement: EWS/BWC aluminium to sash

T/L/R bottom is glass bonded with SIKA

GLAZING

28mm hermetically sealed IGUs

4mm Planitherm Total+ | 20mm warm edge argon | 4mm low iron (1.5W/m²K U-value overall)

4mm Planitherm One | 20mm warm edge | 4mm low iron (1.4W/m²K U-value overall)

Upgrades: Laminated 6.4mm/6.8mm
 Acoustic laminated 6.8mm
 Toughened safety glass
 Obscure glass
 Solar control option using Suncool
 Self cleaning glass

Warm edge: white/grey/black

Fill: Argon gas

DB reduction: Standard 4mm glazing – 34db

 Acoustic 6.8mm glazing – 37db

CERTIFICATION

Air permeability: Class 3

Water tightness: 12208/2000

Wind resistance: A4

PAS 24: Optional upgrade to BS7950/SBD/PAS 24:2016/PART Q

OPTIONS

Raked head

Arched head

Gothic head