



FRONT ELEVATION



SIDE ELEVATION



REAR ELEVATION



SIDE ELEVATION

EXTERNAL FINISHES

ROOF

EXISTING ROOF FINISH IS TO BE REINSTATED IN MATCHING SLATES.

WALLS

EXISTING EXTERNAL WALLS ARE TO BE REPAIRED, RE-RENDERED & RE-POINTED AS NECESSARY TO MATCH EXISTING FINISHES. (SEE ELEVATIONS)

WINDOWS

NEW WINDOWS ARE TO REPLACE EXISTING WINDOWS IN ORIGINAL OPENINGS (SIZE TO REMAIN THE SAME). WINDOWS TO BE DOUBLE GLAZED SOFTWOOD SLIDING SASH OR CASEMENT WINDOWS, FINISHED WITH A GLOSS WHITE PAINTED FINISH.

DOORS

NEW DOORS ARE TO REPLACE EXISTING DOORS IN ORIGINAL OPENINGS (SIZE TO REMAIN THE SAME). DOORS TO BE HARDWOOD DOORS & FRAMES WITH GLOSS PAINTED FINISH TO CLIENTS CHOICE.

GENERAL

ALL RENOVATION WORKS TO THE EXISTING BUILDING ARE TO BE CARRIED OUT IN A MANNER AND STYLE SYMPATHETIC TO THE CHARACTER OF THE ORIGINAL DWELLING.

SHDC
Planning & Development
- 1 NOV 2005
Ref: 1495/05

DETERMINED
PLAN

CONTRACT MILBANK FARM, MILBANK. HOLBEACH, LINCOLNSHIRE.	TITLE PROPOSED ELEVATIONS.	CLIENT MR L. D. CADE				Stour Valley Design planning & building design Telephone 01255 870352 Swan Corner, Mill Lane, Bradfield, Essex. CO11 2UT	SCALE 1:50.	DRAWING NO.
			P	10705	PRELIMINARY - ISSUED FOR APPROVAL.		DATE OCTOBER 2005.	102-2005-01 ^P
			REV	DATE	DESCRIPTION.		DRAWN S. TANKARD	