General Notes.

The southern side of the site boundary hedge to be planted with - Crataegus monogyna Hawthorne, 90 off, standard size and planted at 2.0m centres.

The eastern end of the site to be planted with Fagus sylvatica Beech , 20 off, standard size and planted at 3.0m centres.

All trees to be protected with spral plastic rabbit guards.

Appropriate grass and weed control and any herbicde application undertaken in the planting areas will be completed in accordance with the manufacturers instructions.

The control of grass and weeds will be for the first 3 years as will the checking of rabbit guards.

Maintenance of the trees will extend to 10 years after completion of the scheme. There will be regular inspections of the planted areas and aftercare will include replacement of faliures during the maintenance period.

C & G CONCRETE LIMITED

UFFINGTON ROAD, STAMFORD, LINCS, PE9 2HA
Telephone Stamford 01780 482888
Fax. No. Stamford 01780 480066

LONG SUTTON PLANT

TREEPLANTING SCHEME

DATE	SCALE	DRAWN	DRG No
03/07/03	1:1000	T.R.	GE50

Reproduced From The Ordnance Survey 1=2500 Scale Map TF4023-TF4123 With The Permission Of The Controller Of Her Majesty's Stationery Office. Crown Copyright Reserved. Licence No. 100004926 Date 04/07/03

COPYRIGHT © C&G CONCRETE LTD. 2003

SHDC
Planning & Development
07 JUL 2003
Ref 0852/03

DETERMINED PLAN

