







PROPOSED SIDE ELEVATION




PROPOSED SIDE ELEVATION




PROPOSED FRONT ELEVATION




PROPOSED REAR ELEVATION



PROPOSED ROOF LAYOUT



PROPOSED FLOOR LAYOUT



LEVEL DWELLING APPROACH

Provide a level approach to the principle entrance door no steeper than 1:20 and at least 900mm wide, with cross falls no greater than 1:40. Approach surface material to be firm and non slip, capable of supporting the weight of a wheel chair and its user (loose material such as gravel and shingle would not be unsuitable).

ACCESSIBLE LEVEL DOOR THRESHOLDS INTO THE BUILDING

Entrance door to have an accessible level threshold provided with a weather bar (maximum height 15mm) with suitable drainage channel. Landings to have a fall of 1:40-1:60 away from the door. Principle entrance door to have a minimum 775mm clear opening between the door leaf and doorstops.

RAINWATER DRAINAGE

Rainwater goods to be new 110mm UPVC half round gutters taken and connected into 68mm dia UPVC downpipes. Rainwater taken to new soakaway, situated a min distance of 5.0m away from any building, via 110mm dia UPVC pipes surrounded in 150mm granular fill. Soakaway to be min of 1 cubic metre capacity (or to depth to Local Authorities approval) with suitable granular fill with geotextile surround to prevent migration of fines. If necessary carry out a porosity test to determine design and depth of soakaway.

NOTES

Do NOT scale from this drawing or any other prepared by JDA in connection with this project
This drawing is copyright and may not be altered, traced, copied, photographed or used for any purpose other than for which it has been issued without written permission of the copyright holder.
The Contractor is to check all dimensions on site and report any discrepancies PRIOR TO commencing work.
All details shown on this drawing are based upon typical site conditions related to the area. No responsibility can be accepted for abnormal conditions unless they have been reported in detail so that design amendments may be considered.
All works and materials are to be in full accordance with current British Standards, Building Regulations, Agreement Certificates and Manufacturers printed instructions.
All Building Regulations inspections are to be carried out at the appropriate stages of work.

GENERAL

No work to commence until all statutory approvals have been obtained All dimensions are to be checked on site by contractor prior to the commencement of work.
Drawings have been prepared solely for the procurement of statutory approvals. All dimensions are in millimetres. All levels shown are in metres.
No work is to commence on site until all structural calculations have been approved on site by the Building Control authority. Any alterations to the design are to be formally agreed with the Local Authority.
Exact boundary positions are to be determined by reference to the deeds to the property.
Entire structure is to be built within the legal boundaries of the site. Any encroachments over any boundaries are to be formally agreed with adjoining property owners.

HEALTH AND SAFETY

The contractor is reminded of their liability to ensure due care, attention and consideration is given in regard to safe practice in compliance with the Health and Safety at Work Act 1974.
The contractor shall ensure that all health, safety and welfare measures required under or by virtue of the provisions of any enactment or regulations, or the working rules of any industry are strictly complied with.

Hazardous Substances ;

When hazardous substances are identified as being either flammable, toxic, corrosive and explosive, arrangements must be made to ensure that the use, handling, storage and transport of such substances is safe and without risk to health. a written assessment must be made and if the substance is identified as hazardous, necessary control methods, protective clothing and monitoring established.
The employees working with hazardous substances must be fully informed on the hazard and suitably instructed on safe handling/use of the substance.
Safe systems of work ;
Safe systems of work need to be established for all operations of work by relevant supervisors and management. risk assessments will need to be undertaken and where significant, a method statement completed. these need to be reviewed to ensure that they reflect the hazards, bearing in mind the constantly changing nature of a construction site.
Should there be any changes to established safe systems of work, these require to be referred to the originator, whereby revised risk assessments and method statements can be produced.

Adequate arrangements must be make to keep workplaces in a clean, orderly and safe condition.
provide and maintain safe means of access to and from all working areas and keep clearly marked as appropriate.
The environment of the workplace shall be safe and without risk to health. satisfactory levels of lighting, temperature, dust, noise, etc., must be maintained.

The requirements of the health and safety at work etc. act 1974 and all duties and obligations imposed by the act, management of health and safety at work regulations 1992 and the construction (design and management) regulations 1994; and all other acts and regulations are to be complied with.

Plant and machinery ;
all plant and machinery must be used correctly and be safe and without risk to health. only competent persons may operate plant and machinery and be trained where necessary.
All plant and machinery must be inspected, serviced and maintained as necessary, all of which shall be properly documented.
Statutory tests and thorough examinations will be undertaken where necessary and correct documentation be maintained.

The contractor will provide and maintain a working environment which is safe and without risk to the health of both its employees and persons who may be affected by its employees.

DEMOLITION - WHERE REQUIRED TO FACILITATE THE DEVELOPMENT

Measures to be put in place during and after the demolition to ensure the protection of the public, public amenities and adjoining properties.

Such measures to include:

- The shoring of adjoining buildings.
- The control of dust and noise generation.
- The weatherproofing of any parts of adjoining buildings which are left exposed by the demolition.
- The repairing and making good any damage to any adjacent building effected by the demolition.
- The removal of material or rubbish resulting from the clearance and demolition of the site.
- The disconnection, sealing or removal of any drain or sewer, as required.
- The making good of any disturbed ground.
- Any arrangements necessary for the disconnection off all services (e.g. gas, water, electricity).

Consultation with the Health and Safety Executive, and Fire Authority should be sought if burning structures or materials on site.

If the demolition is more than 50m³ in volume a formal notice of demolition is to be given to building control at least six weeks before any demolition work starts, in accordance with The Building Act 1984: Sections 80-83.

Consultation to be undertaken with the occupiers of adjacent buildings where applicable and a Party Wall agreement put in place. A planning application to demolish to be made where required.

All demolition work to comply with the Construction (Design and Management) Regulations 1994 and a Health and Safety plan is to be provided by the principal contractor.

If applicable, reference should be made to the Construction Design Management Plan.

MATERIALS AND WORKMANSHIP

All works are to be carried out in a workmanlike manner. All materials and workmanship must comply with Regulation 7 of the Building Regulations, all relevant British Standards, European Standards, Agreement Certificates, Product Certification of Schemes (Kite Marks) etc. Products conforming to a European technical standard or harmonised European product should have a CE marking.

CDM REGULATIONS

The Client must abide by the Construction Design and Management Regulations 2015. It is the client's responsibility to appoint a Principal Designer in relation to CDM 2015. For the avoidance of doubt, John Dickie Associates are NOT engaged as the Principal Designer on this project

HEALTH AND SAFETY

The contractor is reminded of their liability to ensure due care, attention and consideration is given in regard to safe practice in compliance with the Health and Safety at Work Act 1974.
The contractor shall ensure that all health, safety and welfare measures required under or by virtue of the provisions of any enactment or regulations, or the working rules of any industry are strictly complied with.

LEAD WORK AND FLASHINGS

All lead flashings, any valleys or soakers to be Code 5 lead and laid according to Lead Development Association. Flashings to be provided to all jambs and below window openings with welded upstands. Joints to be lapped min 150mm and lead to be dressed 200mm under tiles, etc. All work to be undertaken in accordance with the Lead Development Association recommendations.
Lead sheet in lengths not exceeding 1500mm for flashings where roofs abut the external brickwork are to be provided. Combined step and cover flashing fixed in position with lead wedges min. 25mm horizontal joint.
Flashings to be continuous with trays min. 150mm above roof abutment and weepholes every 4th perpendicular.

LEAD VALLEYS

Lead-lined valleys to be formed using Code 5 lead sheet. Valley lead and two tiling fillets to be supported on min 19mm thick and 225mm wide marine ply valley boards on either side of the rafters. Lead to be laid in lengths not exceeding 1.5m with min 150mm lap joints and be dressed 200mm under the tiles.
Roofing tiles to be bedded in mortar placed on a tile slip to prevent direct contact. Valley to have a minimum 100mm wide channel (125mm minimum for pitches below 30°).
All work to be in accordance with the roof cladding manufacturers and the Lead Development Association recommendations.

John Dickie Associates
Chartered Building Engineers
5, Victor Way, Cherry Holt Road,
Bourne, Lincs PE10 9PT
Tel 07778 297733 jda@ndirect.co.uk

Proposed Residential Development at
Millhaven, Lowgate, Gedney
Lincs PE12 0BL

Drawing :
Detached Garage Details

Client : Mrs L. Sale
September 2017
Scale 1 to 125
Drawing No JDA/2017/880/GARAGE.001

PLANNING APPLICATION DRAWING