



Section AA

Inner slope 2:1, outer slope 1:1, top of bank 1.5m wide, topsoil removed under bank and bank keyed into subsoil as shown. Depth below ground 1.5m, bank height above ground 2.5m. Min distance from edge of bank to top of bank on IDB dyke = 12m

External bank will need rapid seeding and establishment of grass cover to prevent erosion due to steepness.

