

Highstock Drain

I.D.B. Drain Easement
& Field Access

Landscaping & Boundary Treatment
Tree Planting to be 1.8m - 2.2m high suitably staked and tied
bp - *betula pendula* Silver Birch
pa - *prunus avium* Wild Cherry

Native Mixed Species Hedgerow
70% hawthorn : 30% mixed species - blackthorn, hazel, field maple, holly
30-50cm in double staggered rows 5 plants per metre run.
to plot frontage and planted inside 1.2m high timber post & rail fencing to rear boundary

Rear gardens to be divided by 1.8m high timber closeboard fence.
Front & Rear Gardens to be turfed
Driveways to be permeable (gravel / granite chippings) with tarmac apron
in verge onto highway in accordance with LCC Highways specification.

Drainage
Foul Drainage - install Package Treatment Unit in accordance with Building Regulations and other relevant legislation. Discharge of treated water to suitably sized proprietary soakways
(Soakways subject to satisfactory soil percolation tests in accordance with BRE 365)

Surface Water Drainage - Roof water to discharge into suitably sized and located soakways in accordance with Building Regulations.


Note
New hedgerow and fence to be set back 1metre from back of existing footpath to provide visibility to adjacent field access

existing footpath

Note
New Vehicular Access to be constructed in accordance with LCC Specification and Construction Details for standard Light Duty flexible dropped crossing

Highstock House

Highstock Lane



Location Plan

1:1250 scale




Gedney Hill



Site Layout

1:250 scale



Plot 2
(under construction)

Plot 3
(current application ref H07-0036-21)

Plot 4
(current application ref H07-0039-21)