LANDSCAPING & TREE LANDSCAPING

G – MIXED HEDGING
- (a) Hawthorn (Crataegus Monogyna)
- (b) Beech (Fagus Sylvatica)
- (c) Blackthorn (Prunus Spinosa)
- (d) Buckthorn (Rhamnos Cathartica)

TREE PLANTING TO CONSIST OF NATURE SPECIES: -

A – SLIVER BIRCH (BETULA PENDULA) FEATHERED
B – HAWTHORN (CRATAEGUS MONOGYNA) FEATHERED
C – WHITE BEAM (SORBUS ARIA) FEATHERED
D – BEECH (FAGUS SYLVATICA) FEATHERED
E – BLACKTHORN (PRONOS SPINOSA) FEATHERED
F – TURKISH HAZEL (CORYLUS COLURNA) FEATHERED

All planting to be in accordance with BS 4428:1989 and amendment No. 1 (1991)

All trees to be planted with minimum 0.6m plastic mulch mat and to be staked, tied and tubed.

1/3 to ½ bag of peat free tree and shrub planting compost to be incorporated into backfill for each tree hole.

— SL ROADWAY STREET LIGHT

WEST DROVE NORTH
Parking
Reception
Toilets
Treatment Plant
Site Manager's Office Accommodation
TOURING CARAVANS
LAKE
Island
Bridge
EARTH BUND
ACCESS ROADWAY
Road Planings
20m
55m
Tarmac ACCESS
LINE
EXISTING FRONT HEDGE TO BE RETAINED EXCEPT WHERE NEW ACCESS IS TO BE CREATED.
9m
Pond
NORTH ROAD
Maple House
New Leaf
Bungalow
Hillgate Farm
DETERMINING PLAN

GOLF COURSE
Access
Pt.0020 4.210ha.
Hillgate Farm
North Road
SCALE 1/2500

AMENDED PLAN
Ref. A-1

ref:	revision	date:
H	ROADWAY LIGHTS.	JULY '05
G	RE-POSITION RECEPTION.	JUNE '05
F	AS-BUILT RECEPTION	FEB '05
E	SITE MANAGERS OFFICE - AMENDMENT.	OCT '04
D	ANNOTATE TREE PLANTING	OCT '04
C	CARAVANS, TOILETS & RECEPTION	JULY '04
B	CONDITION COMPLIANCES	APRIL '04
A	FRONTAGE HEDGE NOTE	APRIL '03.

G. R. MERCHANT BSc (Hons) I.ENG AMICE FIWO

ARCHITECTURAL, STRUCTURAL AND LAND DRAINAGE CONSULTANTS

Unit 4, Wrights Mews
12A Park Road, Holbeach,
Spalding, Lincs. PE12 7EE
Tel: 01406 490600
Fax: 01406 425744
E-Mail: G. R. Merchant @ Merchant. FS. Co. UK

Project
CHANGE OF USE
NORTH ROAD
GEDNEY HILL
SPALDING LINCS

SHDC Planning & Development 11 JUL 2005 Ref: 06/1100

Client
S. KENNALLY

Drawing
SITE & LOCATION PLANS
[FISHING LAKES & AMENITIES]

Job Ref. 546/02
Drawing No. 01H
Date DEC 2002
Drawn GRM
Scales 1/500 1/2500

DO NOT SCALE FROM THIS DRAWING

This drawing is copyright and may not be altered, traced, photographed or used for any other purpose other than that for which it is issued. The General Contractor is to check all dimensions on site and report any discrepancies to the Architect. All details shown on this drawing holistically - foundations are based upon typical site conditions related to the area. No responsibility can be accepted for abnormal conditions which may be discovered during construction unless reported to the Architect so that design ammendments may be considered. Site soil surveys are recommended in respect of foundations to establish specific site conditions before foundation work is undertaken. This drawing is limited in the amount of information contained and does not purport to contain a full specification of the works. It is solely for the purpose of obtaining Planning / Building Regulation approval. This drawing must not be used as a contract document alone. The works will not be supervised or inspected on site by G R Merchant or any representative thereof. It is the client or their appointed agents responsibility to control workmanship, substitution of materials, adherance to specification, variations to contract etc.

All materials to be new unless otherwise stated and all components and materials etc. to be used, fitted and installed etc. in strict accordance with manufacturers instruction and relevant code of practice. Materials shall conform to appropriate British standard specification or BBA certificate or European code equivalent. The Employer / Client shall ensure that the selected contractor is conversant with and adopts all measures necessary to achieve compliance with Health and Safety legislation for Building sites and Work places. The Employer / Client is advised that should the works need to comply with the Construction (Design and Management) Regulations an independent / Planning Supervisor will be required. The works shall comprise of all that is shown on the drawings and details. Work that may not specifically shown but may be reasonably inferred as necessary to carry out the works shall be deemed to be included.