

From: [Gedney, David](#)
To: [_planningadvice](#)
Subject: FW: H07-1115-21 (Mr N Shortland)
Date: 02 December 2021 17:04:18
Attachments: [Wavin Storm Water Management Aquacell Soakaway Design.pdf](#)

Please scan email and attachment – 6SUP (Percolation Tests)
Regards

David Gedney | Senior Planning Officer | **South Holland District Council**
dgedney@sholland.gov.uk
DDI: 01775 764468 |
www.sholland.gov.uk

Please note that any informal officer opinion expressed by this email is without prejudice and is not binding on the Council during the consideration of any formal application.



From: G R MERCHANT LTD <grmerchant.arch.cons@gmail.com>
Sent: 02 December 2021 16:52
To: [_planningadvice](#) <planningadvice@sholland.gov.uk>
Cc: Gedney, David <DGedney@sholland.gov.uk>
Subject: H07-1115-21 (Mr N Shortland)

Mimecast Attachment Protection has deemed this file to be safe, but always exercise caution when opening files.

This message originated from outside your organization

Hello Planning,

Please can you add the attached percolation test document to this application.

Regards
Hannah

G R Merchant Ltd
01406 490800
www.grmerchantltd.com

WAVIN Stormwater Management

AquaCell Soakaway designed in accordance with CIRIA 156

Project & Site Details

Project Number	S21222 - Front Soakaway	Produced by	Mark Henly
Client	Morton & Hall Consulting Ltd	Checked by	
Site Name	Plot 8 Off West Drove South, Gedney Hill, Spalding,		
Location	Lincs	Date	17/11/2021

Drainage Details

Area	90 m ²	Climate Change	0 %
Catchment Type	Roof	Effective Area	81 m ²
Area Reduction Factor	0.9	Additional Inflow	0.00 l/s

Discharge Parameters

Infiltration Rate	1.11E-04	Soil Type	Unknown
Factor of Safety	2	Source	S.I.R
Effective Infiltration Rate	5.56E-05		
Additional Outflow*	0.00 l/s	Depth to Groundwater (m)	Unknown

*flat rate from pump only

Rainfall Data

R value					0.4		Storm Return Period			1 in 30 years	
M5-60					19		Country			England and Wales	
								Storage		Time To	
Time	Z1 Value	y mm	Z2 Value	p mm	Value i	a	b	Height	Half -Empty		
5min	0.38	7.22	1.44	10.40	0.12	-5.82	0.421	0.201	0.37		
10min	0.52	9.88	1.46	14.42	0.09	-3.88	0.421	0.263	0.45		
15min	0.63	11.97	1.47	17.60	0.07	-3.06	0.421	0.306	0.50		
30min	0.80	15.20	1.51	22.95	0.05	-1.82	0.421	0.346	0.54		
1hr	1.00	19.00	1.51	28.69	0.03	-0.95	0.421	0.327	0.52		
2hr	1.19	22.61	1.52	34.37	0.02	-0.37	0.421	0.211	0.38		
4hr	1.44	27.36	1.51	41.31	0.01	-0.02	0.421	0.019	0.04		
6hr	1.59	30.21	1.49	45.01	0.01	0.12	0.421	-0.111	-0.32		
10hr	1.81	34.39	1.49	51.24	0.01	0.24	0.421	-0.237	-0.88		
24hr	2.35	44.65	1.45	64.74	0.00	0.36	0.421	-0.363	-2.01		
48hr	2.69	51.11	1.41	72.07	0.00	0.42	0.421	-0.424	-3.16		

Soakaway Parameters

Length	2.0 m	Width	2.0 m
Depth	0.4 m	Void	95 %

Results

Critical storm duration (hrs)	30min	
Required Storage Height (m)	0.346	PASS
Half Time Empty (hrs)	0.54	PASS

AquaCell Modular Units

No. Units Long	2	No. Units Wide	4
No. Units Deep	1		
Total Number of Units	8	Unit Type	Unknown



CONNECT TO BETTER

WAVIN Stormwater Management

AquaCell Soakaway designed in accordance with CIRIA 156

Project & Site Details

Project Number	S21222 - Rear Soakaway	Produced by	Mark Henly
Client	Morton & Hall Consulting Ltd	Checked by	
Site Name	Plot 8 Off West Drove South, Gedney Hill, Spalding,		
Location	Lincs	Date	17/11/2021

Drainage Details

Area	115 m ²	Climate Change	0 %
Catchment Type	Roof	Effective Area	104 m ²
Area Reduction Factor	0.9	Additional Inflow	0.00 l/s

Discharge Parameters

Infiltration Rate	1.11E-04	Soil Type	Unknown
Factor of Safety	2	Source	S.I.R
Effective Infiltration Rate	5.56E-05		
Additional Outflow*	0.00 l/s	Depth to Groundwater (m)	Unknown

*flat rate from pump only

Rainfall Data

R value					0.4	Storm Return Period			1 in 30 years	
M5-60					19	Country			England and Wales	
Time	Z1 Value	y mm	Z2 Value	p mm	Value i	a	b	Storage Height	Time To Half -Empty	
5min	0.38	7.22	1.44	10.40	0.12	-6.62	0.379	0.206	0.38	
10min	0.52	9.88	1.46	14.42	0.09	-4.42	0.379	0.271	0.47	
15min	0.63	11.97	1.47	17.60	0.07	-3.49	0.379	0.316	0.53	
30min	0.80	15.20	1.51	22.95	0.05	-2.08	0.379	0.360	0.58	
1hr	1.00	19.00	1.51	28.69	0.03	-1.09	0.379	0.345	0.56	
2hr	1.19	22.61	1.52	34.37	0.02	-0.43	0.379	0.230	0.42	
4hr	1.44	27.36	1.51	41.31	0.01	-0.04	0.379	0.030	0.07	
6hr	1.59	30.21	1.49	45.01	0.01	0.12	0.379	-0.111	-0.31	
10hr	1.81	34.39	1.49	51.24	0.01	0.26	0.379	-0.255	-0.93	
24hr	2.35	44.65	1.45	64.74	0.00	0.40	0.379	-0.400	-2.19	
48hr	2.69	51.11	1.41	72.07	0.00	0.47	0.379	-0.469	-3.47	

Soakaway Parameters

Length	2.5 m	Width	2.0 m
Depth	0.4 m	Void	95 %

Results

Critical storm duration (hrs)	30min	
Required Storage Height (m)	0.360	PASS
Half Time Empty (hrs)	0.58	PASS

AquaCell Modular Units

No. Units Long	2.5	No. Units Wide	4
No. Units Deep	1		
Total Number of Units	10	Unit Type	Unknown



CONNECT TO BETTER