


Contractor to check all Dimensions on site prior to ordering materials / commencing work. Do Not Scale from this Drawing - If in doubt then please ask



BLOCK COMPARISON TABLE (each sheet is 1/2 value of 0.35m ² /m ²)		
Manufacturer	100mm Thick Block Type	Full Fill Course Equivalent Thickness
Thermalite	Shield	65mm
Thermalite	Flaxite	65mm
Thermalite	Agilit	65mm
Thermalite	Stratite	65mm
Thermalite	Flaxite	100mm
Thermalite	Hewellite	65mm
Thermalite	Liposite	65mm
Thermalite	Topcrete	100mm
Thermalite	Durox Supabloc	65mm

30x5 m/s straps (S) over 2m, trusses of max 2m c/c to be able to be used in 500mm of ridge purlin under each strap.

Note: Provide 50-50 timber noggins for partition head fixing and pendant light fixings. Position of light fixings to be agreed on site with client.

Solid pork void between rafters and blockwork with mineral fibre insulation and solid timber pokes.

Note: Provide 50-50 timber noggins for partition head fixing and pendant light fixings. Position of light fixings to be agreed on site with client.

Solid pork void between rafters and blockwork with mineral fibre insulation and solid timber pokes.

Note: Provide 50-50 timber noggins for partition head fixing and pendant light fixings. Position of light fixings to be agreed on site with client.

Solid pork void between rafters and blockwork with mineral fibre insulation and solid timber pokes.

Note: Provide 50-50 timber noggins for partition head fixing and pendant light fixings. Position of light fixings to be agreed on site with client.

Solid pork void between rafters and blockwork with mineral fibre insulation and solid timber pokes.

Note: Provide 50-50 timber noggins for partition head fixing and pendant light fixings. Position of light fixings to be agreed on site with client.

Solid pork void between rafters and blockwork with mineral fibre insulation and solid timber pokes.

Note: Provide 50-50 timber noggins for partition head fixing and pendant light fixings. Position of light fixings to be agreed on site with client.

Solid pork void between rafters and blockwork with mineral fibre insulation and solid timber pokes.

Note: Provide 50-50 timber noggins for partition head fixing and pendant light fixings. Position of light fixings to be agreed on site with client.

Solid pork void between rafters and blockwork with mineral fibre insulation and solid timber pokes.

Note: Provide 50-50 timber noggins for partition head fixing and pendant light fixings. Position of light fixings to be agreed on site with client.


Solid pork void between rafters and blockwork with mineral fibre insulation and solid timber pokes.

Note: Provide 50-50 timber noggins for partition head fixing and pendant light fixings. Position of light fixings to be agreed on site with client.

Solid pork void between rafters and blockwork with mineral fibre insulation and solid timber pokes.

Note: Provide 50-50 timber noggins for partition head fixing and pendant light fixings. Position of light fixings to be agreed on site with client.

Solid pork void between rafters and blockwork with mineral fibre insulation and solid timber pokes.



PROPOSED INTEGRAL FLOOR JOISTS SPEC'N

Solid herringbone strutting @ mid point to span over 2m. Strutting at third points to span over 4m.

Provide solid blocking at the ends of herringbone strutting and under straps between last joist and wall.

30x5 m/s anchor straps (S) @ 2m c/c with solid strutting beneath. Notch straps into minimum 3m joists and fix with two nails.

FOUNDATIONS

Existing building area to be stripped of all vegetable matter and rubbish to a min depth of 150mm before excavation commences. Concrete mix for foundations to be GEN13 in accordance with BS5328 1981. Foundations to external wall to be min 700mm wide x 225mm deep. Excavate down to solid firm strata in 750mm deep (min 1000mm if soil is of a shrinkable nature). Exact depth to suit conditions on site and to the strict approval of the L.A. Building Inspector. Any irregularities in subsoil during excavation to be brought to the immediate attention of the Building Inspector & advice to be sought from a Chartered Structural Engineer.

WALLS BELOW D.P.C.

1st Course of Class B brickwork & 2nd course of Red Engineering brickwork below D.P.C. on outer face and 1st course of 71/11mm2 on inner skin of cavity face. Elsewhere in the wall 71/11mm2 concrete. 1st course of full width trench blocks. Batts to be within 225mm of D.P.C. level. Cavity to be filled to within 225mm of below D.P.C. with lean concrete mix.

GROUND FLOOR

150mm mortar screed with a light gauge rebar. Reinforcement to be 8mm gauge pyralite separating layer on 40mm Galvalume (BS 5593) rigid insulation board or similar approved, provide 30mm thick perimeter insulation between screed and floor insulation upto d.p.c. level on 150mm thick GEN13 concrete sub-floor on a 1200 gauge DPM topped onto D.C. within walls on min 150mm clean and well compacted hardcore. Depth of hardcore must not exceed 600mm and must be compacted in 150mm thick layers. All services entering to be sealed with pressure sensitive tape. Floor to achieve a min 'U' Value of 0.25w/m²/K. (See Insulation Installation guidelines under screed).

1. Install a Damp Proof Membrane (DPM) below the slab OR apply a liquid waterproofing material to the top surface of the slab.

2. The DPM must provide continuity with D.P.C. installed within the surrounding walls.

3. Level the surface of the slab; it should be smooth and free of projections.

4. Use a thin sand bedding on a rough tapered slab to ensure that boards are continuously supported. Cut strips of board upwards to fit around the perimeter to eliminate head bridging at steel edges.

5. Upstand depths should equal the sum of the slab insulation and screed thickness.

6. The upstand thickness should not exceed the combined thickness of wall plaster and skirting.

7. Lay boards directly onto the prepared slab cutting infill boards as required. Joints must be tightly butted. The use of a polythene vapour control layer over the insulation is recommended by the BRE to minimise the risk of condensation forming at the insulation/slab interface.

8. Apply a sand/cement screed over the 603-002 boards to a minimum thickness of 65 mm. Use scaffold boards or other protection to prevent wheelbarrows and other traffic damaging boards.

9. Allow screed to dry thoroughly before an impermeable surface, such as a vinyl floor finish, is applied.

10. These recommendations are suitable for normal domestic floor loadings. If higher loadings are required it may be necessary to increase screed thickness and provide reinforcement within the screed.

Installation guidelines (under slab): Insulation under the slab must have Level and well blatted hardcore. DPM (Damp Proof Membrane) placed under insulation. Insulated upstand thickness of slab < screed. DPM contiguous with the D.P.C. Vapour control layer (e.g. 1000 g polythene) laid directly over insulation.

DAMP PROOF COURSE (D.P.C.) Horizontal heavy duty polythene (1000 g) or similar approved to all walls in accordance with BS 6545 and set min 150mm above all external ground levels. D.P.C. in walls must be linked / lapped with DPM in ground floor. Provide perforated cavity wall trays above windows & doors with weep vents at a max of 2m centres with a min of 2m pre-capping.

60mm Sand/Cement screed to BS8204

Concrete slab

Foundation

Insulation

Concrete slab

Foundation

Insulation

Concrete slab

Foundation

Insulation

EXTERNAL WALLS

All external walls to be 275mm overall thickness comprising of:

-100mm Facing Brickwork to be advised.

-75mm cavity filled with Crown Dittlams (or equal approved) built in as work progresses. Insulation batts should be kept clean and free from mortar droppings, all joints should be closely butted. Any cutting and fitting should be neatly done and not distort the layers of glass wool which comprise the material. All D.P.C.s should be installed to ensure that penetrating water is directed only to the outer leaf.

-100mm Thermalite Slab Insulating blockwork.

Continue wall insulation at least 150mm below top of perimeter floor insulation and support off wall ties.

External wall to achieve a min 'U' Value of 0.35w/m²/K.

CAVITIES

Close all cavity walls of joints with Thermalite or similar approved Insulated cavity closers fitted strictly in accordance with manufacturer's instructions. Roof insulation to be continuous with cavity insulation. Install Insulated Cavity Closers by Thermalite or equal approved. Show thick & 75mm wide (to equal cavity width) at joints and ends of all openings in masonry cavity walls. Secure with the proprietary clips provided at maximum 500mm centres. Ensure that closers fit tightly to each other and to the lintel. The closer at the joint must completely fill the closer at the sill.

WALL TIES

Stainless steel cavity wall ties to BS1243 1978 to be built into cavity wall as works proceed and spaced at 750mm centres horizontally, 450mm centres vertically and 300mm staggered around all openings. Ensure wall ties are level or at least sloping to the outside leaf. Bed ties a minimum of 50mm into each leaf and ensure wall ties are completely free from mortar droppings.

LINTELS

All lintels to cavity wall to be factory insulated Birtley Superglaze range unless noted otherwise or equal approved. All lintels must have a min 100mm endbearing and installed in accordance with manufacturer's instructions. Do not allow masonry to overhang lintel by more than 25mm. Note: Lintels are not to have a continuous battenplate.

WINDOWS & DOORS

All windows to be White uPVC to clients requirements based on styles shown on elevations. Fit with 4000mm² trickle ventilators to Kitchen, Utility, Bathroom & En-Suite windows and 8000mm² elsewhere all in accordance with manufacturer's recommendations. Patio doors to be fitted with 10000mm² ventilators. Opening vents to give 1/20 th of floor area rapid ventilation to all rooms. All glazing within 800mm of floor level and within 300mm of a door to a height of 1500mm of ground level to have toughened glass in accordance with Section 11 of the Building Regulations and BS6262 class 9 All double glazed units to be installed in accordance with BS 6262 and to have a 18mm Air gap with a soft Low E coating on glass inner pane to achieve a min 'U' value of 2.0.

1. All windows all windows to have a perimeter weathered both internally and externally and to be fully draught sealed. Provide frosted glass to all Bathrooms, W.C.s and En-Suite windows. Ensure windows & doors are fitted within masonry reveal in overlap cavity closer by min. 40mm to avoid cold bridging.

ROOF FINISH

Concrete Interlocking Double Pantile fixed in accordance with manufacturers instructions and in accordance with BS 5334 Part 1 and 2 Set out to give true lines and regular appearance, fitting neatly at all edges, junctions and features. Fix roof covering to make the building sound and weathertight at the earliest opportunity. Repair any defects as quickly as practicable to minimise damage and nuisance & keep gutters and pipes free of debris and clean out at completion. Provide 50x25 preservative treated timber battens. Tiling battens should be not less than 12m long and continuous over at least 3 trusses. They should be fixed to every rafter member which they cross, or on which they are joined, with nails in accordance with BS5534 Part 1. The ends of the battens should be seen square and butt jointed centrally on a rafter member so that adequate bearing and nailing can be provided for each end of each batten. Butt joints in battens should be arranged so that not more than one batten in four is joined on any one rafter. Generally all tiles at perimeter of roof to be clipped and nailed. Use Code 4 Lead flashing to any abutments with min 75mm upstand.

Specialist diminishing trusses built off 100 x 22 valley boards with Glass Fibre Valley Troughs.

Construct dormer windows from 100 x 50 timber framing, 150 x 50 timber joists to form head number. Fix externally 12mm thick exterior grade WBP plywood sheathing ensuring to allow expansion gaps of 3mm at joints. Fix breather membrane to outer face of sheathing. External finish to side of dormer to be agreed on site with client. Solid pork internally with mineral fibre insulation and supply between insulation and p'board a 500 gauge vapour barrier.

Dotted line shows 25 x 100 diagonal and longitudinal wind bracing, and ceiling bracing to be free from all major defects and any weak points and fixed off in accordance with manufacturer's details. Join joints (if required) to be taken over 2m trusses all in accordance with BS5268 Part 3 - 1985. Bracing to be fixed with 2m 3.35 x 65mm galvanised round wire nails at each cross over and to be firmly butt against walls.

Pre-fabricated Attic Trussed Rafters to Main Bungalow & standard Fink Trusses to kitchen, lounge & Loft space as shown on proposed plan to be at min 1.80 and max 1.40 falls. Fall of drains from gutters to be 1:40. All drains passing thro' walls to have concrete invert of wall with 50mm space around filled with compressible material and opening masked with durable rigid sheet to prevent ingress of vermin or back fill. Drains must not be any lower than foundation depth unless min of 1m from any building. Provide redoubt access to all changes in bends and junctions. Contractor to ensure no live drains run beneath proposed works.

RAINWATER DRAINAGE

Underground drains to be as rainwater drainage but with uPVC guttering and downpipes to clients approval. Falls for guttering to be 1:400 and brackets fixed at max 2m c/c. Downpipes to be connected into underground drains via reducing adapter. Underground drains to be 110mm Ø 0.9mm uPVC or similar approved with flexible joints laid on 100mm gravel and min 150mm surrounds laid to 1:100 falls to new soakaway. Soakaway specification detailed elsewhere.

CEILING

All ceilings to be 15mm plasterboard to BS1230. Ceilings to be have Cove and skin finish to clients requirements. Plasterboard sheets to be fixed with joints staggered and must be laid perpendicular to all joist runs. Fix boards at a min 150mm centres.

ROOF / LOFT ACCESS

Provide insulated roof access trap door with a fully weathered sealed frame and a 38mm brass ball or to clients requirements.

ROOF INSULATION - SLOPED CEILING (OVER BATTEN APPLICATION)

The whole area of the sloped ceiling to be insulated with 25mm thick Multi-Layer Tri-Lo Super 9 Insulation to achieve a 'U' value of 0.19w/m²/K fitted strictly in accordance with manufacturer's instructions.

1. Unroll the insulation preferably vertically, starting from the top of the roof.

2. Staple the insulation product at 500mm centres onto the rafters.

3. Overlap the widths by min 50mm and max 100mm and tape with approved tape i.e. TOSOL-ESIF ALU Tape.

4. Fix the 25 x 50 timber cross battens, breathable roof underlay, counter battens and 50 x 25 tile battens prior to fixing roof covering as described elsewhere.

Roof Insulation 'U' Value Calculation sheet available on request.

ROOF VENTILATION

Install Tylex® or similar approved Breathable Membrane in accordance with manufacturer's instructions which are fully described below. A BBA certificate 09/3635 (Fourth Issue) for Tylex® membrane is available. Use of any film, any shape or any size under all types of roof covering including light jointed and fully interlocking tiles and synthetic slates. Installing Tylex® underlay in accordance with the above certificate will enable a roof to meet all the requirements of the Building Regulations.

Installation Guidelines

Tylex® SUPER should be installed with min 150mm overlap as a standard bituminous felt underlay and secured with stainless steel staples or large headed galvanised chnails. Eaves:

There is no need to provide any vents into the loft at eaves, because a Tylex® non-ventilated roof system does not rely upon air movement beneath the membrane to avoid damage by condensation. To avoid water ponding beneath the fascia of closed eaves and to prevent prolonged exposure of the membrane to ultra-violet radiation, use a Tylex® Eaves Carrier. Stop the membrane short of the fascia and lap it onto the Eaves Carrier Pack closed eaves with fibrous insulation to reduce thermal bridging.

Warp detail:

Lap the Tylex® underlay 50mm onto the gable or flying rafter.

Ridge/hip detail: Extend the Tylex® underlay 150mm from each slope and overlap it at the ridge/hip line. There is no need to provide vent at the ridge.

Valley detail:

Extend the Tylex® underlay from each slope by 150mm beyond the valley centre line and seal the lap using Tylex® Butyl Tape to form a water-tight seal.

Abutments:

Turn up the Tylex® underlay beneath flashings not less than 50mm.

Penetrations:

Seal around all penetrations using Tylex® Butyl Tape.

HEATING SYSTEM

Provide a Low Pressure hot water Central heating system with Gas Fired Boiler and cylinder complete with fan assisted flue exit combustion air vent area of vent is to be strict accordance with manufacturer's recommendations. Boiler to have a SEDBUK rating of 85%. Electrical operated boiler control interlocks are to control the operating periods of the boiler which in turn is controlled by a room thermostat positioned in proposed living room. The boiler should only fire when the space heating or the Cylinder thermostat calls for heat. All radiators are to be fitted with thermostatic radiator valves. The hot water cylinder is to be insulated with a factory applied PU foam coating at least 35mm thick having a min density of 30kg/m³. All space heating pipework located outside the building fabric insulation layers to be wrapped with insulation material having a thermal conductivity of 0.040 not exceeding 0.035 W/m²/K and a thickness equal to the outside diameter of pipe upto max. of 40mm. It should be noted that central heating and hot water pipework in unheated areas may need increased insulation thicknesses for the purpose of protection against frost, refer to BRE Report No. 262 2002 Edition. Oil storage tank should have hot surface beneath such as concrete or paving slabs at least 40mm thick extending out at least 300mm beyond the perimeter of the tank (or external skin if it is of the integrally banded type). Depending on location of oil storage tank fire protection may be required see site plan.

COMMISSIONING OF HEATING AND HOT WATER SYSTEM

Contractor to submit a Certificate to show that commissioning has been successfully carried out. The certificate should be made available to the client and signed by the contractor. A suitable certificate should be published on the part of the Building Regulations. Commissioning and Servicing of Central Heating Systems. A blank copy may be included with the boiler manufacturer's installation instructions or from CH Information Centre Tel: 01926 423 284.

LATERAL RESTRAINT STRAPS

The roof structure to be braced with 30x55 galvanised mild steel straps at max 1.8m c/cs where rafters and ceiling joists run parallel to blockwork walls. Also fit at max 1.8m c/cs to anchor wallplate to blockwork wall with min 3m fixings per strap. Horizontal lateral restraint straps should be spaced at max 2m centres and attached to at least 3 timber members through the use of masonry and packing. Attach to timber members with four steel screws or four 4mm x 75mm m.u.s. with fixings into masonry and two into each joist for force. The timber members should be 100mm at the centre of an uncut block or brick. Vertical restraint strapping should be at least 1m long. Where rafters are fixed to masonry, hardwood nails BSWS x 75mm long or wood screws into place at 12 x 95mm long should be used. The number of fixings should be in accordance with the design and the lowest fixing should be 150mm from the bottom of the vertical strap.

DETERMINED PLAN

11 Nov 1504/05

Shaded areas show critical locations to which require H.F. supplies.

ELECTRICAL INSTALLATION

All electrical work required to meet the requirements of Part P must be designed, installed, inspected and tested by a person competent to do so. Prior to completion of the works the council Building Control Officers must be satisfied that either:

1. An electrical installation certificate issued under a competent persons scheme has been issued or
2. An appropriate electrical installation certificate has been issued for the work, and that it has been signed by a person competent to do so. The Engineer is to advise if any appliance or position of appliance does not conform to regulations. Contractor to seek advice from Client with regard to lighting requirements.

NOTICE PLATES FOR HEATHS & FLUES (Requirement J4)

Information essential to the correct application and use of these fixtures should be permanently posted within the dwelling. A notice plate should be provided containing the following information:

- The location of the hearth, fireplace or the location of the beginning of the flue.
- The category of the flue and generic types of appliances that can be safely accommodated.
- The type and size of the flue and the manufacturer's name and address details.
- The installation date.
- The notice plate should be robust and fitted next to the electricity consumer unit.

SOAKAWAYS

All rainwater to discharge into soakaways and to be min of 5m from any building & a min of 1m² filled with rubble to within 450mm of external ground level. Overlay rubble with polythene sheet and backfill with clean topsoil. Note the soakaway inlet pipe must discharge to the centre of the soakaway in all directions. The contractor should carry out percolation tests to determine the feasibility prior to constructing the soakaways. Detailed below is guidance on how to carry out the tests:

1. Excavate a trial pit to the same depth as the anticipated soakaway below level of the drain.
2. The trial pit should be 300mm x 1000mm wide and 1000 - 3000mm long.
3. It should have vertical sides trimmed square and, if necessary for stability filled with granular material.
4. When no granular material is used, it is advisable to place pegs into the trial pit at the 75% & 25% levels. This allows the water level readings to be taken accurately.
5. The trial pit should then be filled and allowed to drain three times to near empty, with readings taken for:
- The time taken for the water level to lower to the 75% level.
- The time taken for the water level to lower to the 25% level.
6. When granular material is used, a full height, perforated vertical observation tube should be positioned in the pit so that the water levels can be monitored with a dip tape.
7. The trial pit should be filled on three separate occasions to give a true reading on the ground conditions.

Available at this office is a Soil Infiltration check sheet to be completed on site and a copy issued to the L.A. Building Control Officer upon completion.

CHIMNEY CONSTRUCTION

A chimney height of 4.5m or over is normally sufficient for flue draught. The depth of the chimney foundations should be the same as any adjacent wall foundation. In order to provide stability, masonry chimneys should be bonded to, or supported by, adjoining walls of the building. The masonry should be suitable brick, medium weight block or stone and mortar joints. The minimum wall thickness of a masonry chimney is 100mm or 200mm to another compartment or dwelling - see ADJ diagram 2.4. Combustibles must be at least 200mm away from the inside face of the flue liner and 40mm from the outside face. The chimney should be lined with suitable liners and purpose made bands. Joints should be kept to a minimum and sealed with fire cement. Liner joints should be installed with the tongue pointing downward into the socket to contain moisture and condensation in the flue. Any voids between liners and masonry should be filled in accordance with manufacturer's instructions. A flue liner bend is used to create an offset to align the flue with house walling or to reach a chimney pot position. The number of bends should be kept to a minimum for better draw efficiency and to enable sweeping access. They are also used to prevent vertical rain ingress, but this can also be achieved with a suitable cowl. Where more than two bends at 45 degrees are to be used in a flue, additional sweeping access is required by ADJ 1.48. Bends must not exceed an angle of 45 degrees. A structural hearth should be made of solid, non-combustible material such as concrete or masonry of at least 125mm thick. The combustible material should be placed beneath a structural hearth unless there is an air space of 50mm or more on the combustible material is at least 250mm below the top of the hearth. A finished/decorative hearth should be at least 125mm thick and made of non-combustible board/stone material or tiles. For further information refer to ADJ sections 2.22 to 2.29 and 3.40 to 3.42. The fireplace recess should be constructed of solid non-combustible material. Internal solid walls and joints should be at least 200mm thick and cavity walls should have at least 100mm thick leaves and 50mm cavity. Material in the cavity behind the fireplace should be non-combustible. For an open fire the fireplace recess should be at least 350mm deep. For burning solid fuel, ADJ suggests a minimum recess size of 500mm by 500mm using 200mm diameter liners and a flue cross sectional area of 15% of the face area of the fireplace. The height of an unobstructed chimney stack should not exceed 4.5 times the smallest plan dimension of the chimney stack. Please refer to ADJ section 2.10 and diagram 2.1 for recommended positions of the flue outlet above the roof. Details of clearances above easily ignitable roof coverings, such as thatched roofs, are set out in ADJ 2.12 diagram 2.2. A chimney needs to be made weather proof with mortar. Flashing around the chimney pot on a brick or concrete capping with drip overhang. Mortar used for the chimney and flashing should be resistant to rain and frost. Lead flashings are needed at the junction with roof tiles and brickwork to prevent water penetration. A saddle tray damp proof course should be installed across the full span of the stack at the intersection with the roof to prevent water seeping down the chimney. Details of lead saddle trays and flashings are available from the Lead Association. Tel: 01992 656463.

Client: Mr A Davies "Long Acre" 105 North Road Gedney Hill PE12 0NS

Site: Replacement Dwelling

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02

rem 1028 - 02