LANDSCAPING, TREE AND SHRUB PLANTING

A- SILVER BIRCH (BETULA PENDULA) FEATHERED

all planting to be in accordance with BS 4428: 1989 and ammendment no. 1 (1991)

all trees to be planted with minimum 600mm plastic mulch mat and to be staked, tied and tubed

1/ 3 to 1/ 2 bag of peat free and shrub planting compost to be incorporated into backfill for each tree hole

SOFT LANDSCAPING (SHRUBBERY) AREAS

PLANT NAME & SPECIFICATION (for planting season) Oct-Mar only

Berberis Thunbergii - Transplant 1+ 2 450-600mm high
Hedera Helix 'Hibernica' - 300-450mm spread. 9cm.pot. minimum of 3 no. breaks
Ligustrum Ovalifolium 'Aureum - 300-450mm high. 3L.pot
Prunus Lusitanica - 450-600mm high. 3L.pot
Pyracantha 'Soleil D'Or' - 450-600mm high. 3L. pot
Rosa Rugosa 'Frau Dagmar Hastrup' - 300-450mm high. Bare root

N B: AFTER PLANTING 65MM DEEP LAYER OF MEDIUM GRADE BARK MULCH TO BE APPLIED.

SITE LAYOUT

1:100

SILVER BIRCH FEATHERED

A+

B

SHRUB PLANTING

1800mm HIGH CLOSE BOARDED TIMBER FENCE

1800mm HIGH CLOSE BOARDED TIMBER FENCE INSIDE OF EXISTING WALL.

EX WALL BOUNDARY

3 garage

2 garage

1 garage

900

driveway BLOCK PAVED

garden

garden

garden

11500

LINE OF EXISTING BUILDING TO BE DEMOLISHED

Shower

2100

Utility

yard

yard

Shower

1150

Utility

2850

Shower

Utility

yard

4150

4150

4150

4150

Kitchen · Dining

2850

Kitchen · Dining

Kitchen · Dining

drive

Drive under 4150

C 850

C 850

C 850

3200

3200

3200

Living Room

4650

Living Room

Living Room

up

up

up

Hall

Hall

Hall

18000 frontage

low wall

VEHICULAR ACCESS

2000

footpath

EXISTING ACCESS

PROPOSED ACCESS DROP KERBS EXTENDED

1800mm HIGH CLOSE BOARDED TIMBER FENCE

No67

No71

35M X 2M VISIBILITY

H I G H S T R E E T

DETERMINED PLAN

SHDC PLANNING & DEVELOPMENT 06 FEB 2008 Ref. 0156/08