Tree Survey Report & Schedule

01 July 2021

Proposed Residential Development
Land off High Street & Boston Road
Gosberton

Refer to Dwg No. L-WOO-074-SLPX Rev 1

Tree No.	Species	Stem Dia. (cm)	Canopy (m)				Height (m)	Condition	Proposal
			N	S	E	W			
T1	Apple (Malus)	18	2.2	2.2	1.8	2.5	6	Fair	Removal
T2	Apple (Malus)	30	3.8	2.5	3.0	2.0	4.5	Fair	Removal
T3	White Beam (Sorbus Aria)	10	2.2	1.6	2.5	1.7	6	Good	Removal
T4	Ash (Fraxinus Excelsior)	25	3.4	3.3	3.6	3.2	12	Good	Removal
T5	Pine (Pinus Nigra)	40	3.6	3.4	3.6	2.9	12	Good	Removal
T6	Copper Beech (Fagus Sylvatica f. Purpurea)	33 (multi)	2.0	3.2	2.7	2.3	6	Good / Fair	Removal
T7	Silver Birch	35	3.4	3.9	4.9	5.2	11	Good	Removal
T8	Copper Beech (Fagus Sylvatica f. Purpurea)	17 (multi)	3.2	3.6	3.6	3.4	6	Good / Fair	Removal
T9	Goat Willow (Salix Caprea)	35	4.4	3.5	3.5	4.0	5	Good	Retained if possible (see note below)
G1	Tree Group	Various	Various				Various	Good	Retained
H1	Wild Hedgerow	Various	Various				Various	Good	Retained & trimmed back
H2	Wild Hedgerow	Various	Various				Various	Good	Retained & trimmed back

Notes
The above schedule should read in conjunction with existing Site Layout Plan Dwg No. L-WOO-074-SLPX Rev 1, which contains details of the above trees, tree groups and hedgerow.

T9 is situated adjacent to the proposed SUDS Attenuation Pond. This tree should be retained if possible.

T1, T2, T6, T7 T8 are all within the developable area and will need to be removed.

T3 to T5 will need to be removed to allow for maintenance of the open drain.

G1 are located outside the developable area and are therefore unaffected by the porposals. These trees are to be retained with no remedial works required.

H1 is a dense wild hedgerow located along the northern bounadry and provide excellent screening from properties to the north. It is propoposed to retain this hedgerow but will reqire trimming back to make good.

H2 is dense wild hedgrow located along the southern boundary within the open drain. This hedgerow is outside of the development area and will be retained. It will be managed as part of the maintenance of the open drain