



COPYRIGHT
Origin Design Studio has prepared and issued this document to the named client and associated professionals related to this project. Origin Design Studio retains ownership. We do not give permission for reproduction and editing without consultation and our approval.

Key	
Ref.	Description
	Integral swift boxes (Manthorpe Swift Brick or equivalent) installed 4-6m above ground level. boxes positioned 1m apart
	pole mounted barn own box, north facing
	Integral bat box, min 3m above ground. (ibstock integral bat box or similar)
1	Area of longer grass, seeded with general purpose wildflower meadow seed mix. (emorsgate EM1 mix or Boston seeds SS1M mix). Managed as detailed in CGC Ecology preliminary ecological appraisal report.
2	Piles of stone, rubble & logs forming habitats as specified in CGC Ecology preliminary ecological appraisal report.
3	1.2m post and wire fence. To maintain commuting routes for hedgehogs
4	Tarmac resurfacing of existing concrete
5	Existing native hedgerow retained

Rev.	Description	Date	Checked
A02	Issued to Client & Ecologist	24/10/2023	RWDC
A01	Issued to Client & Ecologist	13/09/2023	RWDC

Client
Mr & Mrs Wheeler

Project Title
New Dwelling

Site Details
Corner of Cheal Road/ Saltfleet Lane,
Gosberton Fen, Spalding
PE11 4BD

Title
Landscaping & Ecology Plan

Drawing Number
J1931-BR-02

Print Size
1:200 @ A1



Origin Design Studio Ltd
Holly House, Meadow Lane
South Hykeham, Lincoln LN6 9PF

T. 01522 405100
E. info@origindesignstudio.co.uk
www.origindesignstudio.co.uk

RIBA
Chartered Practice

Planting Schedule Hedgerows

Quantity	Name	Common name	Form	Height (at planting)	Root	Maintenance	Maintenance time of year	Maintenance frequency
136 - single row - 500 centres	Leylandii	100% Leyland Cypress	Transplant	4ft	Bare	- Trimming - Reshaping - Chemical weed control along baseline - Manual weed control - Fertilising - New Planting - Litter/ debris removal - Watering	- April - October - Hard prune October - February - In winter and summer and only where other methods of control have failed - Throughout - Spring - October - March - Throughout - As necessary depending on weather conditions - largely May August	- 2 x annually - Annually if required - Annually - Monthly - Annually - Annually, if required - Daily - As required - daily in dry spells

Planting Schedule Trees

Quantity	Name	Common name	Form	Height (at planting)	Girth (at Planting)	Root	Maintenance	Maintenance time of year	Maintenance frequency
2	Acer campestre	Field Maple	Standard	2.5 - 3m	8 - 10cm	28L Pot	- Inspection of mature trees - Selective felling of over mature/ declining specimens - Selective thinning of planting - Pruning and repair of wounds - Removal/ adjustment of stakes and ties - Watering - New planting to broaden/ supplement diversity of tree stock Review of tree survey information & tagging - Review of tree survey information and tagging - Other works - removal of debris trapped in branches	- March - September - October - February - October - February - As necessary following inspection - As necessary depending on weather condition. Largely May - August - October - March	- Annually - As required - Every 10 years - As required - As required - As required - daily in dry spells - Annually - or as required
1	Quercus robur	pedunculate oak	Standard	2.5 - 3m	8 - 10cm	28L Pot		- March - September As necessary following inspection	- Every 5 years - As required

