


BRICK TYPE A:
LEICESTER MULTI CREAM



BRICK TYPE B:
LEICESTER RED STOCK



BRICK TYPE C:
IVANHOE WESTMINSTER



BRICK TYPE D:
OAKMOOR CREAM



ROOF TILE E:
CONDORN CONCRETE
SLATE BLACK



ROOF TILE F:
CONDRON CONCRETE
PANTILE TERRACOTTA



ROOF TILE H:
MARLEY LINCOLN CLAY
SINGLE PANTILE



LEGEND

- PRIVATE PATHS: BUFF RIVEN PAVING SLABS
- METER BOXES: RECESSED WHITE GRP
- RAINWATER GOODS: HALF ROUND GUTTERS 68MM DIA. DOWN PIPES BLACK UPVC
- EXTRACT GRILLE: BLACK UPVC
- WALL FLUE TERMINAL: BLACK UPVC
- ROOF FLUE TERMINALS: BLACK UPVC
- BRICK TYPE A: LEICESTER MULTI CREAM
- BRICK TYPE B: LEICESTER RED STOCK
- BRICK TYPE C: IVANHOE WESTMINSTER
- BRICK TYPE D: OAKMOOR CREAM
- ROOF TILE E: CONDORN CONCRETE SLATE BLACK
- ROOF TILE F: CONDRON CONCRETE PANTILE TERRACOTTA
- ROOF TILE J: MARLEY LINCOLN CLAY: SINGLE PANTILE

REV	DATE	DESCRIPTION
M	12.01.2024	Updated to latest site layout
L	08.06.2023	Weatherboard removed, plots 2,3,12,16 Rutland-V
K	20.02.2023	Weatherboard added to plots 2,3,12 & 16
J	06.02.2023	Roof Tile F - change from slate to pantile
I	22.07.2022	PLOTS 1,2,32,33,37,38 UPDATED TO BRICK TYPE C
H	30.06.2022	ROOF TILE F SPEC UPDATED
G	24.06.2022	UPDATED TO LATEST BRICK AND ROOF TILES
F	01.11.2021	ADDITIONAL DIMENSIONS ADDED TO REAR OF PLOT 32 ON LA REQUEST.
E	20.10.2021	PLOT 32 & 33 AMENDED
D	19.10.2021	PLOT 32/33 DRIVE SHORTENED
C	24.09.2021	POS AREA ENLARGED
B	17.09.2021	UPDATED TO NEW LAYOUT
A	15.07.2021	UPDATED TO NEW LAYOUT

ASHWOOD HOMES
1 Goodison Road, Lincs Gateway Business Park,
Spalding, Lincs, PE12 6FY **T: 01406 490590**

PROJECT:
PROPOSED RESIDENTIAL DEVELOPMENT AT FEN ROAD, PHASE 2
HOLBEACH

DRAWING TITLE:
MATERIALS SCHEDULE LAYOUT

SCALE: 1:500 @ A1	DATE: 8.06.2023
DRAWN: AR	REV: M

DRAWING No:
127 - MSL - 01