




Existing storage areas to be converted to residential units in the manner shown.

Provide injected DPC to walls where lacking.

Existing ground floors to be painted with 2 no. coats of Synthesprufe waterproof and then covered with 60mm Celotex insulation and 19mm moisture-resistant decking.

Trim openings in first floor to suit new staircases where shown. Trimmers to be 75mm x depth of existing joists. Existing first floor joists are approx. 225mm deep.

Provide new cavity walls where shown to provide separation.

Provide 100mm stud partitions where shown to form room separation.

Sound Insulation
Use Robust details as follows:-
Ground floor separating walls - Ref. E-WM-1
First floor separating walls - Ref. E-WT-1
Separating walls - Ref. E-FT-1

Existing external solid walls to be dry-lined.

Block up existing openings where shown.

New openings to be formed or existing openings adjusted as shown to suit new windows and doors. Support over with IG Box 200 or L1/S lintels as necessary.

Heating to each unit to be by electric storage radiators. Hot water to be by electric instantaneous heaters.

Connect foul drains to existing foul drainage system as shown.

Foul drains under building to be encased in 150mm concrete.

Make good to all disturbed and affected areas.

Roof Ventilation
At eaves provide proprietary ventilation equivalent to a 10mm continuous gap along eaves.

Kitchen Ventilation
Provide proprietary mechanical extract ventilation unit capable of extracting 60 l/sec. Alternatively provide proprietary cooker hood capable of extracting 30 l/sec.

Bathroom/En-suite Ventilation
Provide proprietary mechanical extract ventilation unit capable of extracting 15 l/sec. System to offer intermittent operation.

Safety Glazing
Provide safety glass to all windows to a minimum height of 800mm above floor level plus doors to a minimum height of 1500mm above floor level. Side screens to be same as doors if within 300mm of doors.

Smoke Detection
Provide mains operated self-contained smoke alarms to BS5446 Part 1 in accordance with Approved Document B1.

Wall Construction
275mm cavity walls to consist of:
100mm face brickwork (see site plan for details), 75mm cavity to be filled with Crown Dritherm full fill insulation in accordance with BBA Certificate No. 86/1678 or similar approved, 100mm internal skin of Celcon standard blocks or similar approved to give 0.35 U-value. Cavity walls tied together using galvanised iron or plastic twist ties spaced 900mm horizontally and 450mm vertically to BS1243, 1978. Internal blockwork walls to receive 10mm sand/cement render and skim finish. Robust details in accordance with T50, 2001.

Habitable Room Trickle Ventilation
Provide proprietary trickle ventilators to head of windows giving a total opening area of not less than 8000mm²

Kitchen/Utility/Bathroom/WC Trickle Ventilation
Provide proprietary trickle ventilators to head of window giving a total opening area of not less than 4000mm²

Foul Water Drainage
Underground drainage to be proprietary 110mm diameter p.v.c. pipes flexible jointed to fall 1:70 bedded in 100mm pea gravel. Under building drains to be encased in 150mm pea gravel with lintel over pipes at wall abutments. Where drain passes through wall, provide suitable protection to prevent gas ingress to building. 110mm diameter soil and vent pipe to extend 900mm above window head and to terminate in balloon finial. Soil and vent pipe to be fitted with access plate at base. Provide suitably sized wastes from all appliances (in accordance with Approved Document H) complete with minimum 75mm deep sealed traps and rodding eye access points at every direction change. All above ground drainage to BS5582 and all underground drainage to BS8301. Provide seal plates both sides of pipe entry to avoid vermin entry.

Protection to Underground Pipes
Where pipes are not under road and have less than 600mm cover concrete paving slabs should be laid as bridging above the pipes on minimum 75mm pea gravel. If flexible pipes are under a road and have less than 900mm cover reinforced concrete bridging should be used instead of paving slabs. Provide compressible material below slab/concrete.

Inspection Chamber Construction
Proprietary polypropylene inspection chambers bedded on 150mm concrete. Form protective 255mm thick concrete collar around head of inspection chamber with 300mm projection from cover. Covers to be Grade C light duty unless inspection chambers are in driveways where Grade B medium duty covers are to be used.

Foundations
As indicated on plan provide concrete strip foundations. To cavity walls provide 700mm wide x 225mm thick and to 100mm walls provide 450mm wide x 225mm thick, unless noted otherwise. To non-load bearing internal walls thicken out ground floor oversite concrete to 450mm wide x 200mm thick. Widen foundations at chimney breast accordingly and make 300mm thick. Foundations to be taken down to an approved firm base, subject to local authority specifications. Concrete to be ST3 grade unless noted otherwise. Proximity of existing and proposed trees are to be taken into account in accordance with N.H.B.C. chapter 4 when determining foundation depth.

Provide a firm level approach to front entrance of minimum width 900mm. Gradient of approach to be no steeper than 1:20. At entrance to building threshold to be maximum 15mm high.

External access door that serves as access to ground floor WC to have a minimum clear opening width of 775mm.

Ensure minimum 900mm corridor width, access to ground floor WC with no obstructions (radiators, etc.) to corridor area adjacent doors

Sockets, light switches, TV points, doorbells to habitable rooms to be positioned between 450mm and 1200mm above floor level.

Internal Lighting
Provide energy efficient lights that only take lamps having a luminous efficiency greater than 40 lumens per circuit watt. Examples of lamps are fluorescent tubes and compact fluorescent lamps (note GLS tungsten lamps with bayonet cap or Edison screw bases).

Method of determining number of locations:

Number of Rooms	Recommended min number of locations
1-3	1
4-6	2
7-9	3
10-12	4

Note - Hall stairs and landing count as one room (but may contain more than one fitting).

Excludes garages, lofts and outhouses.

All external lintels to be insulated type.

All external joinery to be fully draught proofed.

Loft hatch to be draught sealed and latched shut.

All doors, windows and any loft hatches to be effectively sealed and draught proofed.

First floor habitable rooms shall have means of escape windows with openings of at least 450mm wide x 450mm high and a minimum area of 0.33m². Escape windows to be within 1.1m of floor.

Provide ½ hour fire protection between flats - walls and ceilings.

Existing stairs serving flat above shop to have support for half landing adjusted as necessary to make way for access through to WC area.

Where now drains connected to main sewer in Fleet Street all works for connections to be to Anglian Water requirements.

Sound Insulation

Floors
Fill the void of the timber joists with 100mm SoundSlab.

Fix to the underside of the timber joists, SoundBreaker Resilient Bars at right angles at every 400mm centres.
Fix a double layer of 12.5mm SoundBloc plasterboard to the underside of the SoundBreaker bars, ensuring all layers are staggered and sealed around the edges with appropriate acoustic sealant.

Apply Reduc Foundation 35 as a structural floor throughout, ensuring that the appropriate Isolation Tape is used around the perimeter of the rooms, with all joints of the boards glued together using Reduc Joint Adhesive and sealed round the edges with FlexiSeal Acoustic Sealant.

Separating Walls
Separating walls to consist of two 38mm x 89mm timber frames with a 52mm clear cavity between, clad on each room face with one layer of 19mm plasterboard plank and one layer of 12.5mm plasterboard. One frame to contain 50mm mineral wool/glass fibre. The estimated mass of the separating wall structure is 46kg/m².

Note
The above sound insulation will be subject to a pre-completion Sound Test.

To opening in 350mm walls support over with IG Box 500 lintel and L10 Lintel.

Existing first floor joists are approx. 225mm deep.

Provide escape lighting to the common areas of the flats.

Cavity walls to be insulated only where they are external walls.

Shower rooms without windows to have extractor fan with 15-minute overrun with suitable ducting so as not to affect sound transmission.

All above ground drainage to be to BS5582.

The total rise from ground floor to first floor is 2.7m.

Private Stairs
Stairwell formed by timber trimmers and load bearing walls (see plan). Provide timber balustrading to open side of stairs 900mm above pitch line and 1000mm high to stairwell opening to act as guarding and to be capable of resisting a horizontal force of 0.36 KN/m. Balustrading to be vertical type, not horizontal or ranch style. No parts of stairs to have any gaps greater than 99mm. Provide timber handrail to top of balustrading or independently 900mm above pitch line. Ensure minimum headroom above pitch line is 2000mm. Total rise: See plan. Maximum rise: 220mm. Minimum going: 220mm. Maximum pitch: 42°. Read in conjunction with Approved Document K.

Remove existing wall where shown dotted.

Fill in existing stairwell with joists and boards to match existing.

Commissioning of Heating and HWS Systems

A competent person, i.e. the main contractor or sub-contractor shall supply a Certificate of Satisfactory Compliance with Building Regulations Part L. A copy of which shall be made available to both the client and the Building Control body.


A suitable set of operating and maintenance instructions are to be made available to the client to explain to the householders how to operate the systems so that they can perform efficiently and what routine maintenance is advisable for the purpose of the conservation of fuel and power.

Lintels
All coded lintels as stated in Schedule or marked on plan to be by I.G. To be installed in strict accordance with manufacturers instructions. Form d.p.c. cavity tray above all lintels. To all exposed lintels i.e. not sheltered from overhanging eaves, etc. to have proprietary weepholes to joints of brickwork at approximately 450mm c/c. To be confirmed on site with Building Control Surveyor.


Opening at eaves level to be L1/E lintels by I.G. or similar approved.

Sub-structure Walling
100 mm Class A dense concrete blocks. Bitumen felt d.p.c. to external walls 150mm above ground level. Weak mix infill to base of cavities to terminate 225mm below lowest d.p.c. level.

Roof Insulation
To roof spaces provide proprietary 300mm thick fibreglass insulation laid as 100mm between joists and 200mm across joists or equivalent to give 0.25 U-value. Ensure a gap of 50mm between roof underfelt and quilt at all times.



C - IMF. ADDED - 11.12.06
B - DESIGN. ALTS. - 4.12.06
A - DESIGN. ALTS. - 7.11.06




PROPOSED CONVERSION OF STORAGE AREAS TO RESIDENTIAL UNITS AT REAR OF 39-41 HIGH STREET, HOLBEACH FOR

MR. & MRS. R. RICKERBY.

DETERMINED PLAN

1:50 1:500 SD06-069/1
OCT-06 B.GILHAM.

2 Edinburgh Walk, Holbeach, Spalding, Lincs. PE12 7AP.
Tel: 01406 424343 Fax: 01406 490702



Doorway clear opening width (mm)	Corridor/Passageway width (mm)
750 or wider	900 (when approached head-on)
750	1200 (when approached not head-on)
775	1050 (when approached not head-on)
800	900 (when approached not head-on)

All windows to give minimum 1/20th of floor area as ventilation and to be double-glazed.

Glazing
All windows and doors to be double-glazed with minimum 16mm spacing and to use Pilkington 'K' glass or similar approved, efficiency of 0.05.

THIS DRG. TO BE READ IN CONJUNCTION WITH SD06-069/2, SD06-069/3, SD06-069/4, E-WM-1, E-WT-1, E-FT-1