PLOT 1

A YEW - TAXUS BACCATA FASTIGIATA - FEATHERED
B YEW - TAXUS BACCATA FASTIGIATA AUREA - FEATHERED
C CEDAR - CEDURUS DEODARA - FEATHERED

PLOT 2

D BEECH - FAGUS SYLVATICA - FEATHERED
E RED HAWTHORN - CRATAEGUS PAULS SCARLET - FEATHERED
F WHITEBEAM - SORBUS ARIA LUTESCENS - FEATHERED
G SILVER BIRCH - BETULA PENDULA - FEATHERED

All planting to be in accordance with BS 4428:1989 and amendment No. 1 (1991)

All trees to be planted with minimum 0.6m plastic mulch mat and to be staked, tied and tubed.

1/3 to 1/2 bag of peat free tree and shrub planting compost to be incorporated into backfill for each tree hole.

N

SCHOOL PLAYING FIELD

Chain Link Fence (school)

1800 Close Boarded Fence

1800

Shed

Greenhouse

House

Conifers

Post & Wire Fence

Gravel

Tarmac

Bungalow

Bungalow

7301

MANOR DRIVE

1200

SITE PLAN

SCALE: 1/250

N

0600

SITE

HOLBEACH

LOCATION PLAN

SCALE: 1/2500

DETERMINED PLAN

HOLLAND DC
PLANNING
24 JAN 1997
Ref:

G. R. MERCHANT
I.ENG AMICE, FIWO,
ARCHITECTURAL, STRUCTURAL
& LAND DRAINAGE CONSULTANT
TEL: HOLBEACH (01406) 490800

PROJECT:
RESIDENTIAL DEVELOPMENT
MANOR DRIVE
HOLBEACH

CLIENT:
DGM PROPERTIES LTD

SCALES:
AS INDICATED

DATE:
APRIL 1996