


BRICK TYPE A:
LEICESTER MULTI CREAM



BRICK TYPE B:
LEICESTER RED STOCK



BRICK TYPE C:
IVANHOE WESTMINSTER



BRICK TYPE D:
OAKMOOR CREAM



ROOF TILE E:
CONDORN CONCRETE
SLATE BLACK



ROOF TILE F:
CONDRON CONCRETE
PANTILE TERRACOTTA



ROOF TILE H:
MARLEY LINCOLN CLAY
SINGLE PANTILE



WEATHERBOARD:
MARLEY ETERNIT CEDRAL
WEATHERBOARDING IN SLATE GREY



LEGEND

	PRIVATE PATHS: BUFF RIVEN PAVING SLABS
	METER BOXES: RECESSED WHITE GRP
	RAINWATER GOODS: HALF ROUND GUTTERS 68MM DIA. DOWN PIPES BLACK UPVC
	EXTRACT GRILLE: BLACK UPVC
	WALL FLUE TERMINAL: BLACK UPVC
	ROOF FLUE TERMINALS: BLACK UPVC
	BRICK TYPE A: LEICESTER MULTI CREAM
	BRICK TYPE B: LEICESTER RED STOCK
	BRICK TYPE C: IVANHOE WESTMINSTER
	BRICK TYPE D: OAKMOOR CREAM
	ROOF TILE E: CONDORN CONCRETE SLATE BLACK
	ROOF TILE F: CONDRON CONCRETE PANTILE TERRACOTTA
	ROOF TILE J: MARLEY LINCOLN CLAY: SINGLE PANTILE
	MARLEY ETERNIT CEDRAL WEATHERBOARDING INDICATED BY RED LINE

REV	DATE	DESCRIPTION
K	20.02.2023	Weatherboard added to plots 2,3,12 & 16
J	06.02.2023	Roof Tile F - change from slate to pantile
I	22.07.2022	PLOTS 1,2,32,33,37,38 UPDATED TO BRICK TYPE C
H	30.06.2022	ROOF TILE F SPEC UPDATED
G	24.06.2022	UPDATED TO LATEST BRICK AND ROOF TILES
F	01.11.2021	ADDITIONAL DIMENSIONS ADDED TO REAR OF PLOT 32 ON LA REQUEST.
E	20.10.2021	PLOT 32 & 33 AMENDED
D	19.10.2021	PLOT 32/33 DRIVE SHORTENED
C	24.09.2021	POS AREA ENLARGED
B	17.09.2021	UPDATED TO NEW LAYOUT
A	15.07.2021	UPDATED TO NEW LAYOUT

ASHWOOD HOMES
1 Goodison Road, Lincs Gateway Business Park,
Spalding, Lincs, PE12 6FY **T: 01406 490590**

PROJECT:
PROPOSED RESIDENTIAL DEVELOPMENT AT FEN ROAD, PHASE 2
HOLBEACH

DRAWING TITLE:
MATERIALS SCHEDULE LAYOUT

SCALE: 1:500 @ A1	DATE: 20.02.2023
DRAWN: AR	REV: K

DRAWING No:
127 - MSL - 01