



JOB NAME:	1 THOMAS DE MOULTON WAY, HOLBEACH
PLANNING APPLICATION NO.	H09-0426-19
SCHEDULE NO:	01
REVISION & DATE	20/07/2020

SCHEDULE OF EXTERNAL MATERIALS & COLOURS

SHEET 1OF2

	MATERIAL	NAME/FINISH	ADDITIONAL INFORMATION	MANUFACTURER	SWATCH	LOCATION
WALLS & ENTRANCES						
1.00	Bricks	Ivanhoe Westminster	Bond: Stretcher. Windows set back 190mm from face of Brickwork in centre of cavity	Manufacturer: Ibstock	 <i>Note: This sample panel shows the correct bricks and brick treatment but note that the mortar is not correct too dark.</i>	All blocks
1.01	Mortar	White mortar mix	Flat, or bagged joints	Castle Cement		All blocks
1.02	Roofing slates	Spanish Classics		IBS Products		Roof
1.03	Intake & Extract Duct	Natural Vent - Inline slate vent	Above kitchen	Roofing Megastore		Roof
1.04	Weep Holes	Product reference: Terracotta micro-wall Weep ventilator	Locations: Through outer leaf immediately above base of cavity, at cavity trays, stepped dpcs and external openings. 75 mm above top of cavity fill at base of cavity.	Toolstation		All blocks
1.05	Windows & Doors - Timber painted White gloss	Stormproof external window/door frame Wooden painted gloss RAL 9010 White				Windows - All blocks Doors - Entrance to residence