LEGEND

	PRIVATE PATHS: BUFF RIVEN PAVING SLABS
	METER BOXES: RECESSED WHITE GRP
	RAINWATER GOODS: HALF ROUND GUTTERS 68MM DIA. DOWN PIPES BLACK UPVC
	EXTRACT GRILLE: BLACK UPVC
	WALL FLUE TERMINAL: BLACK UPVC
	ROOF FLUE TERMINALS: BLACK UPVC
	BRICK TYPE A: LEICESTER MULTI CREAM
	BRICK TYPE B: LEICESTER RED STOCK
	BRICK TYPE C: IVANHOE WESTMINSTER
	BRICK TYPE D: OAKMOOR CREAM
	ROOF TILE E: IMERYS ALPHA 10 SLATE
	ROOF TILE E: IMERYS DOUBLE PANNE S NATURAL RED
	ROOF TILE E: IMERYS ALPHA 10 CHEVREUSE

REV	DATE	DESCRIPTION
J	22.11.2021	PLOTS 48 TO 53 REPLANNED
H	08.09.2021	PLOTS 37 & 38 CHANGED TO 2 BEDS, LINK ROAD REMOVED
G	31.08.2021	AFFORDABLE MIX UPDATED
F	19.07.2021	UPDATED FOLLOWING PLANNING COMMENTS
E	24.06.2021	PLOT 61 & 62 CHANGED TO AS38
D	04.06.2021	PLOT 81 CHANGED TO RICHMOND
C	01.06.2021	PLOT NUMBERS REDUCED TO 81
B	25.05.2021	ADDITIONAL 9 PLOTS INCLUDED
A	18.05.2021	PLOT 1 GARAGE AMENDED

ASHWOOD HOMES
1 Goodison Road, Lincs Gateway Business Park,
Spalding, Lincs, PE12 6FY **T: 01406 490590**

PROJECT:
PROPOSED RESIDENTIAL DEVELOPMENT AT BALMORAL WAY PHASE 2
HOLBEACH

DRAWING TITLE:
MATERIALS SCHEDULE LAYOUT

SCALE: 1:500 @ A0 | DATE: 31.08.2021

DRAWN: AR | REV: J

DRAWING No:
75 - MSL - 01