

NATIVE TREES AND SHRUBS MAINTENANCE AND PLANTING

Trees and shrubs to be maintained, for five years after planting. Weeding for the first few years in order to prevent young trees and shrubs being smothered and to reduce competition for water and nutrients. It is important that all planted areas are kept weed free until they become established. To ensure weed growth is adequately controlled the bases of trees and shrubs in grass areas to be kept clear for at least half a metre from around the plant, mulch immediately on planting for weed control and a suitable granular herbicide may need to be applied to all areas after planting. Proposed trees to be planted with native tree and shrub mix. All pits to be prepared with two-thirds volume topsoil and one-third volume peat free tree and shrub planting compost. Transplants / container grown plants to be planted into prepared 300 x 300 x 300mm pits, light standard trees to be planted in 600 x 600 x 600mm prepared pit. All transplants and standard trees to be protected with 600mm plastic spiral rabbit guard. Feathered trees to be staked with single short stake. All tree planting heights 600-900 mm whips.

TREES

Ash - *Fraxinus excelsior*
Hazel - *Cory avellana*
Oak - *Quercus robur*
Maple - *acer campestre*
Silver Birch - *betula pendula*
Laurel Prunus - *laurocerasus*

SHRUBS

Alder Buckthorn - *Frangula alnus*
Blackthorn - *Prunus spinosa*
Dogwood - *Cornus sanguinea*
Elder - *Sambucus nigra*
Hawthorn - *Crataegus monogyna*

SHDC
Planning & Development
21 AUG 2009
Ref: 0646-09

SUPERSEDED




DC ARCHITECTURAL SERVICES LIMITED

ARCHITECTURAL AND PLANNING SERVICES

THE BARN, PARTNEY MILL, SPILSBY, LINCOLNSHIRE, PE23 4PE

TEL NO. 05601 500536; FAX. NO. 01790 752865

E-mail - dcarchitectural@btconnect.com



Client A. H. Worth and Co Ltd

Project LANDSCAPING, Manor Farm, Holbeach Hurn, Spalding
Lincolnshire. PE12 8LR

Drawing Title TREE PLANTING

Scale 1:500

Date MARCH 09

Drawn DB

Checked

Drawing number

DC/116/01

Revision

A