



Revision:	Date:	Drawn:	Check:
A	extended adoptable road in front of plots 9-12	03-01-24	LEN DNW
B	location of footways and service strips amended and sub station added	29-02-24	LEN DNW
C	Introduced adoptable turning heading in front of plots 41-42.	29-02-24	LEN DNW
D	Adoptable Roads extended to boundary, Plots 31-36 rearranged to allow for paths, Paths to LEAP removed, Substation Moved, Swale introduced.	29-02-24	LEN DNW
E	Schedule updated.	26-03-24	LEN -
F	Added Topographical Survey	15-04-24	LEN DNW
G	Amended Boundary to Title - updated layout to suit amended boundary, Plot 56 changed from 3bed to 2bed. updated Suds and LEAP position due to Drainage Strategy.	28-03-25	LEN DNW
H	Amended House type Codes, updated plots 54-57 to maisonettes, amended footprint of TYPE B & F. Moved substation and introduced Pump station.	22-04-25	LEN DNW
J	Updated roads, attenuation basin and swale, relocated substation and foul pumping station to engineers drawings.	16-05-25	LEN DNW
K	Substation relocated off private drive to south	22-05-25	LEN DNW
L	Additional parking space next to SS, introduced BC Ps & BSP, PD junctions wider. Footpath extended adjacent to FPS. Play Park amended shape and renamed Active Area.	03-07-25	LEN / ADA DNW
M	Primary Road reduced to 5m. Blocked paved Shared surface introduced with traffic calming.	24-10-25	LEN DNW
N	Plots 1-8 moved south, plot 10 changed to a 2 bed house, accommodation schedule updated.	10-12-25	LEN DNW
P	Site entrance updated to match Civils drawing dated 25.12.15	16-12-25	YNM DNW

KEY

- Site Boundary
- BCP

Bin Collection Point
- BSP

Bin Storage Point

Note: all dwellings to have secure loops to attach cycles to on the rear elevation in a convenient location - type tbc.

ACCOMMODATION SCHEDULE										
102-575 Wignals Gate, Holbeach						Date: 04 December 2025				
HOUSE TYPE	Beds	Persons	NUMBER	SQM	SQM Total	SQFT	SQFt total	%	sub %	
TYPE A Masionette	1	2	8	50.00	400.00	538.20	4305.60	14.0%	14.0%	
TYPE B Bungalow	2	4	2	64.00	128.00	688.90	1377.79	3.5%		
TYPE C House	2	4	24	70.40	1689.60	757.79	18186.85	42.1%		
Type H House	2	4	1	82.40	82.40	886.95	886.95	1.8%		
TYPE D House	2	4	1	82.80	82.80	891.26	891.26	1.8%	49.1%	
TYPE E House	3	5	15	82.40	1236.00	886.95	13304.30	26.3%		
TYPE F House	3	5	4	93.00	372.00	1001.05	4004.21	7.0%	33.3%	
TYPE G House	4	6	2	107.00	214.00	1151.75	2303.50	3.5%	3.5%	
TOTALS:			57		4204.80		45260.47	100%		
Total Site Area:			1.65			Hectares				
Total Site Area:			4.077			Acres				
Site Density:			34.55			DPH				
Developable Site Area:			1.24			Hectares				
Developable Site Area:			3.060			Acres				
Developable Density:			18.63			Units / Acre				
Developable Density:			45.97			Units / Hectare				
Sq. Feet/Acre Coverage			14791.00			Sq. Feet/Acre				



Project	Wignals Gate, Holbeach
Status	Planning
Client	D Brown Building Contractors
Package	N/A
Sheet Title	Planning Layout
Scale	1/500@A1
Date	07-12-2023
Drawn by	LEN
Checked by	DNW
Drawing reference	102-575 / 001
Revision:	P

London | Birmingham | Leicester
0203 327 0181 | 0121 309 0071 | 0116 204 5800
rgp.co.uk - designing.co.uk

Notes:
All designs should be constructed in strict accordance with building regulations.
In addition any materials, components and fittings in or connected to a facade should be non-combustible
if the top story of the building is above 11m.
All dimensions to be checked on site. Do not scale off this drawing for construction purposes.
This drawing is the copyright of the architect, and not to be reproduced without their permission.
Creston Survey map information reproduced with permission of HESCO Crown Copyright reserved.
rgp Ltd. Trading as rgp