



FOUL WATER ALL VIA EXISTING 150MM PIPE ALONG DRIVEWAY CONNECTED INTO MAIN SEWER ALONG LOW LANE

ALL REFUSE TO BE STORED AT EACH PROPERTY UNTIL COLLECTION DAY WHEN IT WILL BE TAKEN BY RESIDENTS TO THE DESIGNATED COLLECTION POINT OFF LOW LANE

NOTES:

- FINISHED GROUND FLOOR LEVEL OF ALL PLOTS TO BE SET AT 3.5m AOD NEWLYN
- SURFACE WATER RUN-OFF FROM THE ROOFS OF THE PROPOSED DWELLINGS AND DETACHED GARAGE SHOULD BE DISCHARGED INTO SOAKAWAY CRATES. 120L CAPACITY WATER BUTTS PROVIDED TO THE REAR OF ALL PLOTS TO INTERCEPT AND STORE RAINWATER. THE INFILTRATION SYSTEM TOGETHER WITH ASSOCIATED DRAINAGE SHOULD BE DESIGNED TO BRE DIGEST 365 AND MEET THE REQUIREMENTS OF PART H OF BUILDING REGULATIONS
- FLOOD RESILIENT & RESISTANT CONSTRUCTION UP TO 300mm ABOVE FINISHED GROUND FLOOR LEVEL
- ALL REFUSE TO BE STORED AT EACH PROPERTY UNTIL COLLECTION DAY WHEN IT WILL BE TAKEN TO THE DESIGNATED COLLECTION POINT OFF LOW LANE
- ALL FOUL WATER VIA EXISTING 150MM DIAMETER FOUL WATER SEWER DISCHARGING INTO PUBLIC FW SEWER IN LOW LANE
- 2 No MIN ELECTRIC VEHICLE CHARGING POINTS TO BE PROVIDED TO EACH DWELLING
- EXTERNAL FACING BRICKWORK TO CONSIST RED MULTISTOCK BLEND. ROOF TILES TO BE DOUBLE PANTILES COLOUR TBC. WINDOWS AND DOORS TO BE PVCu AND ALUMINIUM (COLOUR TBC)
- BOUNDARY TREATMENT TO CONSISTS OF TIMBER FENCING, BRICKWORK WALLS, METAL RAILINGS AND HEDGED SEPARATION
- BOUNDARY TREATMENT TO INCORPORATE DISCREET GROUND LEVEL APERTURES TO ALLOW UNRESTRICTED MOVEMENT OF FORAGING WILDLIFE

NOTES:

- ACCESS TO BUILDING FOR FIRE FIGHTING APPLIANCES AND FIRE FIGHTERS TO SATISFY BUILDING REGULATIONS 2010 PART B5
- MINIMUM WIDTH OF 3.7m BETWEEN KERBS FOR VEHICLE ACCESS ROADS
- MINIMUM TURNING CIRCLE BETWEEN KERBS FOR PUMPS TO BE 16.8m. ACTUAL TURNING CIRCLE BETWEEN KERBS 17.52m
- MINIMUM TURNING CIRCLE BETWEEN WALLS FOR PUMPS TO BE 19.2m
- TURNING FACILITY TO BE PROVIDED WHERE DEAD-END ACCESS ROUTE EXCEEDS 20m
- ACCESS ROAD SURFACE TO BE CONSTRUCTED WITH MINIMUM CARRYING CAPACITY OF 18 TONNES FOR PUMPING APPLIANCES
- EXISTING ACCESS WITHIN THE EXTENTS OF THE PUBLIC HIGHWAY TO BE UPGRADED TO A BOUND MATERIAL CONSTRUCTED IN ACCORDANCE WITH LINCOLNSHIRE COUNTY COUNCIL SPECIFICATION
- MINIMUM OF 12 SWIFT BRICKS TO BE INCORPORATED INTO GABLE ELEVATIONS OF SUITABLE PLOTS
- NATIVE WILDFLOWER PLANTING TO BE INCORPORATED INTO THE LANDSCAPING SCHEME TO IMPROVE BIO-DIVERSITY



FIRE FIGHTING APPLIANCE TURNING FACILITY 1:250



SITE PLAN
1:500



Plan Produced for: 47 LOW LANE

Date Produced: 04 May 2020

Plan Reference Number: TQRQM20125083645952

Scale: 1:1250

© Crown copyright and database rights 2019 OS 100042766

- Notes as Applicable
- GENERAL
1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ANY OTHER DOCUMENTS ISSUED FOR THIS PROJECT. THESE INCLUDE CONTRACT DRAWINGS, SPECIFICATIONS & SCHEDULE OF WORKS.
2. ALL BUILDING MATERIALS SPECIFIED SHALL COMPLY WITH THE REQUIREMENTS OF THE CURRENT BUILDING REGULATIONS, BRITISH STANDARDS, BRITISH STANDARD CODES OF PRACTICE AND SHALL BE TO THE SATISFACTION OF THE LOCAL AUTHORITY & CONTRACT ADMINISTRATOR.
3. ALL STRUCTURAL WORKS ARE TO BE CARRIED OUT IN FULL ACCORDANCE WITH STRUCTURAL ENGINEERS' APPROVED CALCULATIONS AND DETAILS AND TO THE SATISFACTION OF THE LOCAL AUTHORITY BUILDING CONTROL OFFICER.
4. ALL WORKS ON SITE TO BE CARRIED OUT IN FULL ACCORDANCE WITH THE CONSTRUCTION (DESIGN AND MANAGEMENT) REGULATIONS 2015 AND CURRENT HEALTH & SAFETY LEGISLATION.
5. THE CONTRACTOR MUST SITE CHECK ALL DIMENSIONS PRIOR TO ORDERING MATERIALS. FIGURED DIMENSIONS ARE TO BE USED FOR TENDER PURPOSES ONLY. DISCREPANCIES MUST BE REPORTED IMMEDIATELY TO THE CONTRACT ADMINISTRATOR BEFORE PROCEEDING.

Project: DEMOLITION OF EXISTING BUNGALOW AND ERECTION OF 4NO. DETACHED DWELLINGS. LAND KNOWN AS 47 LOW LANE HOLBEACH LINCOLNSHIRE PE12 7PW	
Applicant: MR D J RILEY & MR A T RILEY	
Drawing: SITE & LOCATION PLANS	
Sheet Size: A3	
Drawing No: 001	
Date: November 2020	
Scale: As shown	
Revision: Rev D	Drawn: DR
Checked: RR	Approved: DR