



Parkhouse Farm, Harbottle, Morpeth, Northumberland, NE65 7BD
Tel: 01669 650250, E-mail: sk@ruralpartners.co.uk

BACKGROUND STATEMENT

**Manor Farm
Holbeach Hurn, Holbeach
Spalding, Lincolnshire**

**Proposed Extension
to Existing Reservoir**

Ref No. FP/011B/BS October 2017

**Worth Farms Ltd
Fleet Estate Office
Manor Farm
Holbeach Hurn
Spalding
Lincolnshire
PE12 8LR**

1. BACKGROUND

Worth Farms Limited is a subsidiary division of A H Worth & Company Limited (AHW), a family business which has farmed on Holbeach Marsh for over 100 years. The farm, situated on the alluvial silts of South Lincolnshire, is currently cropped as follows:-

Wheat	750 ha
Potatoes	270 ha
Vining Peas	270 ha
Maize	250 ha
Sugar Beet	220 ha
Salad Crops	150 ha

The centre of operations is at Manor Farm, Holbeach Hurn.

A 28 day Prior Approval Application (PP-06443386) has recently been submitted for the amalgamation of the existing reservoirs at the entrance of Manor Farm (top left hand corner of photo) which are used to store surface water from some of the yards and buildings at Manor Farm which extend to nearly 12 ha in total prior to it being disposed of on the surrounding farm land.



Water from the reservoirs at Manor Farm will be pumped to the proposed extension to the existing reservoir where it will be able to store it before using it for irrigation.

Taking the average rainfall for the area to be 575mm (MAFF Technical Bulletin 34 Climate and Drainage) the total annual run off from the farmstead at Manor Farm is in the order

of 69,000 cu m, if only 50% of this could be collected and stored then it would be possible to fill the proposed extension to the reservoir.

2. RESERVOIR DESIGN CRITERIA

The reservoir has been designed with reference to the following:-

Small Embankment Reservoirs; Report 161; CIRIA (Construction Industry Research and Information Association)

Floods and Reservoir Safety: an Engineering Guide; The Institution of Civil Engineers. (*F&RS*)

Freeboard Height

Design Freeboard when full is 0.75m

Fetch	0.25 km	
Average Hourly annual max wind speed	18 - 20 m/s	<i>Fig 3 F&RS</i>
Once in Ten Yearly maximum wind speed	24 - 26 m/s	<i>Fig 4 F&RS</i>
Design Wind Speed assumed	25 m /s	

Using *Fig 9. F&FS* Relationship between effective fetch, wind speed and significant wave height by interpolation

Significant Wave Height 0.35 m

Design Wave Height

Using *Table 2 F & FS* Design Wave Heights

Dam Type	Earth Fill
Crest	Grass
Downstream slope	Random grass
Design wave height factor	1.3
Design wave height	= 0.35 m x 1.3
	= 0.4725 m
	= 0.5 m

Wave Run Up

Using *Fig 10 F&FS* Ratio of run-up height to design wave height

Dam Slope		1 : 4
Slope characteristic		Smooth
By interpolation Run-up Ratio		1.4
Minimum Freeboard Allowance	=	0.5 m x 1.4
	=	0.7 m

NOTE:-

The maximum fetch of 0.25km lies on a South Eastern axis, whilst the fetch on the direction of the prevailing winds (South West) is in fact less than 0.1km.

3. ARCHAEOLOGY

No archaeology was discovered when the existing reservoir was constructed and there is no known evidence of archaeology on the site which has been intensively cultivated over the years.

Should on stripping the site any evidence be found then Lincolnshire County Councils Historic Environment Team will be advised.

4. PLANNING LEGALISATION

The proposed development can be dealt with under the Prior Notification Procedure for the following reasons:-

The reservoir is reasonable necessary for the purposes of agriculture
The development is being carried out on an area of land of greater than 5 ha
The area of the proposed operations exceeds 0.5 ha
No part of the development is within 25 metres of a metalled part of a trunk or classified road
No excavated material will be removed from the unit. (The spoil from the excavation will be used to construct the walls of the reservoir - see appendix ii)

5. CONCLUSION

Prior Approval should be granted for the proposed reservoir so as to enable Worth Farms Ltd to utilise the surface water run off from the farmstead for irrigation thereby assisting in future proofing the business from the affects of climate change.

Simon Kenny B.Sc., I.Eng., M.I.Agr.E.
Rural Partners Ltd
Parkhouse Farm
Harbottle, Morpeth, Northumberland, NE65 7BD

PLANS

FP/011B/125 Site Plan

FP/011B/500 Location Plan

FP/011B/01 Plan and Typical Section

Appendix i

Volume Calculations based on Rectangular Reservoir with

Area of Bottom = 9,300 sq m

A H Worth Extension

Client F. Parnell
Site Proposed Extension

CALCULATION OF RESERVOIR QUANTITIES

7,957,290 Galls
36,169 cu m

Volume above Ground Level

4,710,997 Galls
21,414 cu m

Description

Qty Unit

Bottom Width of Reservoir	61.00	m
Bottom Length of Reservoir	152.50	m
Ratio of Side Slopes (Wet)	4.00	
Ratio of Side Slopes (Dry)	2.50	
Depth of Water	3.00	m
Freeboard	0.75	m
Depth of Excavation below existing G.L.	1.40	m
Depth of Top Soil	0.00	m
Bulk Factor for Top Soil	0.50	
Width of Bank Top	4.00	m
Height of Bank above Ground Level	2.35	m
Width at Mid Depth of Water	73.00	m
Length at Mid Depth of Water	164.50	m
Width at Top Water Level	85.00	m
Length at Top Water Level	176.50	m
Width at Top of Bank	91.00	m
Length at Top of Bank	182.50	m
Area of Bottom	9,302.50	sq m
Area at Mid Depth	12,008.50	sq m
Area at Top Water Level	15,002.50	sq m
Width of Liner	95.92	m
Length of Liner	187.42	m
Area of Liner	17,978.26	sq m
Surface Area of Excavation @ Sub-Soil level	11,819.14	sq m
Area at Mid Depth of Excavation of Sub Soil	10,529.46	sq m
Overall Width of Reservoir Top of Bank	99.00	m
Overall Length of Reservoir Top of Bank	190.50	m
Overall Width of Reservoir @ Sub-Soil level	110.75	m
Overall Length of Reservoir @ Sub-Soil level	202.25	m
Overall Area of Reservoir @ Sub-Soil level	22,399.19	

VOLUMES

Volume of Water Storage in Gallons	7,957,290	galls
Volume above Ground Level	4,710,997	galls
Volume of Sub Soil Excavated	14,756	cu m
Volume of Top Soil Strip	0	cu m
Total Volume of Excavation	14,756	cu m
Volume of Bank	15,162	cu m