

William Stukeley Park, Holbeach

Tree no	Size band	Species	Age class	Condition/ notes	Work required	Priority
1	S2	Salix caprea Sallow	mature	multi-stemmed tree in moderate condition, near phone lines	re-pollard at 0.5 - 1m	3 months
2	S2	Salix caprea Sallow	mature	multi-stemmed tree in moderate condition, near phone lines	re-pollard at 0.5 - 1m	3 months
3	S2	Salix caprea Sallow	mature	multi-stemmed tree in moderate condition, growing under phone lines	re-pollard at 0.5 - 1m	3 months
4	S2	Salix caprea Sallow	mature	multi-stemmed tree in moderate condition, growing under phone lines	re-pollard at 0.5 - 1m	3 months
5	S2	Quercus robur Oak	mature	tree in moderate condition, OHB's to drive, ivy on stem	prune back to drive edge/ fence to clear drive to 3-4m, sever ivy	3 months
6	S2	Sorbus species	mature	2 trees in moderate condition, OHB's to phone wires, ivy on stems	prune back to clear phone lines by 1-2m, sever ivy, clear vegetation here back to the fence line	3 months
7	S2	mixed	mature	group of multi-stemmed and self-set trees with overgrown shrubs along the car park entrance and drive area, OHB's and encroachment to driveway	remove Laurel - behind neighbour -and small self-set Sycamore and Ash, cut vegetation back to expose drive edge, Mahonia can be reduced to approx 1m if an issue, prune Birch trees near the parking bay to clear to 3-4m, sever ivy on bigger stems	3 months
8	S4	Quercus cerris Turkey oak	mature	specimen tree in moderate condition growing in grassed area, some mower damage to roots, some low target deadwood	no action	
9	S2	Juglans regia Walnut	mature	tree in moderate condition growing on the traffic island	no action	
10	S3	mixed	mature	large group of trees growing along the western boundary area, moderate condition, minor deadwood, ivy on some stems	sever ivy	3 months
11	S2	Acer pseudoplatanus Sycamore	mature	multi-stemmed tree in moderate condition, some epicormic growth, self-set Elder at base	remove epicormics and Elder to clean stems	3 months
12	S2	Platanus x hispanica Plane	mature	6 trees near the drive, in moderate condition, OHB's to light and drive way	prune back overhanging branches from light to clear by 1-2m, crown lift all trees to clear drive by 5-6m and back to the kerb-line	3 months
13	S2	mixed	mature	boundary vegetation including self-set trees, in rather poor condition; ivy clad, not a nuisance to neighbour	no action	
14	S2	Taxus baccata Yew	mature	group of trees growing near the wall, in moderate conditon, minor deadwood, OHB's to bus shelter	prune back all to clear bus shelter by approx 1m	3 months
15	S3	Tilia species Lime	mature	tree now in poor condition; now a stump with some living branches, conservation benefit and interest	no action	
16	S4	mixed	mature	large group of trees growing in the northern area of the park and near the wall, in moderate condition, minor deadwood, some ivy clad stems, overhanging branches and vegetation to footpath, landscape and conservation benefits	sever ivy on biggest stems, cut back OHB's to inside the wall and to give 3-4m of clearance to path	3 months
16A	S4	Acer pseudoplatanus Sycamore	mature	tree appears to be in moderate condition; some deadwood at top of the crown, old stem cavitites	remove deadwood in crown	3 months

17	S2	Crataegus monogyna Hawthorn	mature	fallen and hung up tree over footpath	make safe clear of path - could be allowed to regrow from main stem	3 months
18	S2	Tilia species Lime	mature	old coppice tree with several stems, recently coppiced and responding well, growing with area of self-set Elders and unmanaged vegetation	monitor Elder encroachment	
19	S2	Carpinus betulus Hornbeam	mature	tree growing opposite the garage, in moderate condition, ivy on stem, OHB's close to light, road sign and footpath	prune back to main stem to clear all, ensure clear of path by 3-4m	3 months
20	S2	mixed	mature	group of multi-stemmed Elm grown up from suckers next to the wall, self-set Elders, ivy on stems and wall, some OHB's to footpath, minor deadwood	prune to ensure phone lines and path are clear	3 months
21	S2	Taxus baccata Yew	mature	tree in moderate condition, ivy on stem, minor deadwood, OHB's to electric box, phone line	sever ivy, prune OHB's back to clear all by 1-2m	3 months
22	S3	Cuppressus species	mature	group of 5 trees along electric sub-station boundary, had recent stem failures, OHB's to sub-station	reduce all by 6-7m to leave approx 4m high, to reduce risk of failures	3 months
23	S4	mixed	mature	group of trees in the lawn, in moderate condition, includes planted trees protected by tree cages	no action	
24	S3	mixed	mature	group of trees, including specimen conifers, in moderate condition, minor deadwood, ivy on some stems, OHB's to path	lightly prune where required to clear footpath	3 months
25	S4	Fraxinus excelsior Ash	mature	tree in moderate condition, possibly been struck by lightening in past as stem damage and areas of decay down one side, some deadwood, possible early Ash dieback disease	monitor	1 year
26	S2	mixed	mature	group of trees near the garages, including self-set Ash and Elder, vegetation should be checked by mowing here subject of complaints in the past about OHB's and roots encroaching the wall, some footpath lifting	no action	
26A	S2	Elder	mature	self-set tree next to the wall, now pushing against it	fell and treat stump	3 months
27	S4	Acer pseudoplatanus Sycamore	mature	specimen tree growing on or through soil bank, appears to be in moderate condition; stem cavity at 2m and old stub cavities, some ivy on stem and epicormic growth, low target deadwood, conservation and landscape value, possible bat roost site	remove epicormic and ivy to clean stem	3 months
28	S2	Acer negundo	mature	specimen tree in moderate condition, minor deadwood	no action	
29	S3	mixed	mature	scattered group of trees in the lawn, in moderate condition, minor deadwood	no action	
29A	S2	Salix caprea Sallow	semi mature	multi-stemmed tree next to school fence, will become an issue	coppice stems	3 months
30	S4	mixed	mature	scattered group of trees, including those along the school fence area, in moderate condition, minor deadwood, ivy on stems	sever ivy on trees	3 months
31	S5	Sequoiadendron giganteum	mature	specimen tree in moderate condition, with a younger tree nearby in good condition, typical dead lower branches	no action	
32	S4	mixed	mature	scattered group of trees in the lawn, in moderate condition, minor deadwood	no action	
33	S1	Laurel	mature	section of hedge in lawn, causing visibilty issues to driveway	remove section of hedge - approx 4m	3 months
34	S3	Cedrus atlantica Glauca	mature	specimen tree in moderate condition, growing in lawn, some low target deadwood	no action	

35	S3	Carpinus betulus Hornbeam	mature	veteran tree with 3 main stems, old pollard @ 9m, extensive decay and trunk cavity, Ganoderma brackets in cavity, woodpecker nest hole in top of decayed stem, leaning to east, high conservation value; risk of stem failure is outweighed by this	no action	
36	S4	Salix babylonica Weeping willow	mature	tree in moderate condition, has been pollarded in past, soil compaction; foliage appears a bit 'thin', some low target deadwood, old failure scars, possible bat roost site	spread woodchip from tree work around root plate	3 months
37	S4	Acer pseudoplatanus Sycamore	mature	group of trees near the school access and security fence, in moderate condition, probably mainly self-set trees with Yew and some Elders and shrubs, OHB's to path, fence and gate, ivy on stems	crown lift Sycamore to 4m, sever ivy, cut all vegetation back to path edge, prune other trees and shrubs to 'open up' footpaths and entrance - including on triangle between gate and drive	3 months
38	S3	mixed	mature	group of trees and shrubs between the drive and neighbour, in moderate condition, some low branches to driveway and neighbour, ivy on stems, encroaching vegetation	sever ivy on biggest stems, cut back OHB's to the fence line to clear neighbour, clear vegetation next to fence to leave an access strip, and prune to give 3-4m of clearance to drive	3 months
39	S2	mixed	semi mature	group of trees - including Birch, Sallow and self-set Ash and shrubs, growing near the footpath and gate/ fence, ivy clad stems, OHB's to path and fence	pollard Sallow at 1m, crown lift other trees to clean stems, sever ivy on stems, prune back other vegetation/ shrubs to clear school fence, path and parking bay	3 months