



ROOF TILE D:
WIENERBERGER NEW CASSIUS ANTIQUE SLATE



ROOF TILE A:
CONDRON CONCRETE SLATE - BLACK



ROOF TILE E:
MARLEY LINCOLN CLAY SINGLE PANTILE



ROOF TILE B:
CONDRON CONCRETE PANTILE - TERRACOTTA




ROOF TILE C:
CONDRON CONCRETE SLATE - COUNTRY RED

LEGEND


	PRIVATE PATHS: BUFF RIVEN PAVING SLABS
	METER BOXES: RECESSED BROWN GRP
	RAINWATER GOODS: HALF ROUND GUTTERS 68MM DIA. DOWN PIPES BLACK UPVC
	EXTRACT GRILLE: BLACK UPVC
	WALL FLUE TERMINAL: BLACK UPVC
	ROOF FLUE TERMINALS: BLACK UPVC
	BRICK TYPE A: LEICESTER MULTI CREAM
	BRICK TYPE B: LEICESTER RED STOCK
	BRICK TYPE C: IVANHOE WESTMINSTER
	BRICK TYPE D: OAKMOOR CREAM
	ROOF TILE A: CONDRON CONCRETE SLATE: BLACK
	ROOF TILE B: CONDRON CONCRETE PANTILE: TERRACOTTA
	ROOF TILE C: CONDRON CONCRETE SLATE: COUNTRY RED
	ROOF TILE D: WIENERBERGER NEW CASSIUS ANTIQUE SLATE
	ROOF TILE E: MARLEY LINCOLN CLAY SINGLE PANTILE



BRICK TYPE A:
LEICESTER MULTI CREAM



BRICK TYPE B:
LEICESTER RED STOCK



BRICK TYPE C:
IVANHOE WESTMINSTER



BRICK TYPE D:
OAKMOOR CREAM

Rev.	Date	Description
F	13.09.2023	Meter boxes changed to brown
E	13.09.2023	Plots 205-213 amended to suit site layout
D	09.08.2023	Plot 92 side brick wall revised to tie in with HM Phase 1.
C	19.04.2023	Red Line Boundary Amended
B	23.09.2022	Plots 169 to 203 updated. Garages added to plots 208 to 213. House type schedule updated.
A	22.07.2022	Plots 92-95 and 112-118 altered.

ASHWOOD HOMES
1 Goodison Road, Lincs Gateway Business Park,
Spalding, Lincs, PE12 6FY **T: 01406 490590**

PROJECT:
Proposed Residential Development at Holbeach Meadows (Phase 2A)

DRAWING:
Material Schedule Layout. (Phase 2A)

SCALE: 1:500@A1 DRAWN: MII

DATE: SEP.2022 REVISION: F

DRAWING No: 135-MSL-01